

## Noble Energy, Inc. Proposed Best Management Practices Summary

Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-039527. BMP's will be constructed and maintained prior to, or at the beginning of construction. BMP's used will vary according to the location and project phase and will be modified in accordance with the SWMP.

Spill Prevention Control and Countermeasures (SPCC) plans are in place for production facilities regulated by CFR112.

Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be stored and disposed of in accordance with applicable regulations. If spills occur, prompt cleanup will be performed to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.