

EnCana Oil Gas (USA) Inc.
Gap Drilling Plan Prognosis

GAP Name: Parachute GAP **State:** Colorado
Well Name: Federal 25-7BB **County:** Garfield
Pad Name: PH25 **Location (SL)** SE NE 25-7S-96W 1957 FNL 659 FEL
Rig Name **Location (BHL)** SW NE 25-7S-96W 1520 FNL 1980 FEL
GL 6064
KB 22'

Geological Markers	MD	TVD	Comments
OHIO CREEK (Top Kmv)	3653	3456	
WILLIAMS FORK FM	4208	3976	
TOP GAS	4988	4746	
COAL RIDGE (Paludal)	6203	5961	
ROLLINS SS (Iles Fm)	6558	6316	
TD	6758	6516	
Permit TD	6928	6686	

Casing and Cementing Program					
DEPTH	HOLE SIZE	SIZE	WEIGHT	GRADE	CEMENT VOLUME
CONDUCTOR					
0-40'	± 24"	16"	0.25" Wall PE	X42	± 5 yds ready mix (to surface)
SURFACE CASING					
0' - 1100'	12-1/4"	8-5/8"	24#	J-55, STC, New	Lead: 289 sx, 12.5, G extended, 2.11 ft³/sk Tail: 178 sx, 15.8, Class G, 1.16 ft³/sk
NOTE: Lead cement includes excess equivalent to 80% Entire Annulus (Lead and Tail)					
PRODUCTION CASING					
0' to 6928'	7-7/8"	4-1/2"	11.6#	180, LTC, New	Lead: 254 sx, 12, TXI, 1.79 cuft/sk, Tail: 402 sx, 13 TXI, 1.43 ft³/sk, (30% excess each)

MUD PROGRAM				
DEPTH	MUD TYPE	DENSITY	VISCOSITY	LOSS
		lbs/gal	(sec/qt)	(cc)
0' - 1100'	Fresh Water Gel	8.8 - 9.0	28 - 35	NC
1100' - TD	LSND	9.0 - 9.3	35 - 55	10 - 5

ABNORMAL PRESSURES / TEMPERATURES / POTENTIAL HAZARDS

Anticipated BHP 3209 psig 9.2 Anticipated MASP 1738 psig
A cross sections of "sized" lost circulation material will be kept on location during drilling operations as a contingency for any fluid lost circulation. There are no known abnormal pressures, temperatures and/or potential hazards.

LOGGING PROGRAM	
Mud Logger	None Anticipated
Coring	None Anticipated
DST	None Anticipated
Cased Hole Logs	CBL/CCL/GR/VDL/ RST(in lieu of PEX) to be run in accordance with State Regulations
Open Hole Logs	PEX Optional- At Operator's Discretion
Directional Surveys	Once every 200' with MWD in hole. Once every 1000' while vertical.

EnCana Contacts			
Geologist (Primary)	TJ Dewane	Office / Cell	720.876.5495 / 303.518.3630
Geologist (Secondary)	Stacy Rosner		720.876.5581 / 785.393.2447
Engineer (Drilling)	Frank Fernandez		720.876.3442 / 303.250.7849
Engineer (Completions)	Ryan McGilvery		720.876.3681 / 303.358.8684

ADDITIONAL OPERATOR COMMENTS

EnCana requests permission to drill the discussed well in a "S" shaped well design. Visit Master APD for further details.