DRILLING PROGRAM

Well Name: Kupe 2H
Rig: Ensign 970
Date: 30 Jan 2014
Version: 1
Prepared by: Jason Bull
Approved by: Jason Bull

Target Depth: 3,000.0 mMD / 2,999.0 mTVD
Target Formation: Kupe Sand
Total Days: 10.0

Hole Sections

Section	Size (in)	Depth (mMD)
Conductor	30	120.0
Surface	17.5	1,000.0
Intermediate	12.25	2,000.0
Production	8.5	3,000.0

Casing Program

Section	Size (in)	Grade	Weight (ppf)	Connection	Depth (mMD)
Conductor	30	X52	310.0	Welded	120.0
Surface	13.375	L80	68.0	BTC	1,000.0
Intermediate	9.625	L80	47.0	BTC	2,000.0
Production	5.5	L80	17.0	BTC	3,000.0

Mud Program

Section	Type	MW (ppg)	PV (cP)	YP (lbf/100ft²)	Gel 10s	Gel 10m	Gel 30m	FL (cc/30min)	pH	Solids (%)	Sand (%)	Chlorides (mg/L)
Conductor	Spud Mud	8.6	15	20	5	8	10	12	9.0	4	0.5	500
Surface	Spud Mud	9.2	18	25	6	10	12	10	9.0	6	0.5	1,000
Intermediate	KCl/Polymer	9.8	22	30	8	12	15	6	9.5	8	0.5	35,000
Production	KCl/Polymer	10.2	25	35	10	15	18	4	9.5	10	0.5	40,000

Cement Program

Section	Lead / Tail	Slurry	Volume (bbl)	Density (ppg)	Yield (ft³/sk)	Sacks	Top (mMD)	Bottom (mMD)
Conductor	Tail	Class G + 2% CaCl2	50.0	15.8	1.15	244	0.0	120.0
Surface	Lead	Class G + 2% CaCl2	180.0	12.5	2.13	475	0.0	800.0
	Tail	Class G + 2% CaCl2	60.0	15.8	1.15	293	800.0	1,000.0
Intermediate	Lead	Class G + 3% KCl + 0.3% Retarder + 0.2% Defoamer	220.0	12.5	2.13	580	0.0	1,700.0
	Tail	Class G + 3% KCl + 0.3% Retarder + 0.2% Defoamer	70.0	15.8	1.15	342	1,700.0	2,000.0
Production	Tail	Class G + 3% KCl + 0.3% Retarder + 0.2% Defoamer + 0.5% Fluid Loss	95.0	15.8	1.15	464	2,000.0	3,000.0

Bit Program

Run	Size (in)	Type	Manufacturer	Model	Jets (32nds)	Depth In (mMD)	Depth Out (mMD)	Hours	ROP (m/hr)
1	17.5	PDC	Smith	MDSi613	3x20	120.0	1,000.0	18.5	51.4
2	12.25	PDC	Smith	MDSi616	3x18	1,000.0	2,000.0	22.0	45.5
3	8.5	PDC	Smith	MDSi619	3x16	2,000.0	3,000.0	30.0	33.3

Directional Plan

Kick-off Point (KOP): 1,200.0 mMD / 1,199.5 mTVD
Build Rate: 3.0 °/30m
Maximum Inclination: 42.0°
Azimuth: 215.0°
Target Coordinates: 1,850.0 mN, 1,420.0 mE

Survey Program

Survey	Type	Tool	Interval (mMD)	Accuracy
Surface	Gyro	Gyrodata	0.0 - 1,000.0	±0.5°
Intermediate	MWD	Halliburton	1,000.0 - 2,000.0	±0.3°
Production	MWD	Halliburton	2,000.0 - 3,000.0	±0.3°

Contingency Plan

Lost Circulation: Reduce pump rate, add LCM (10-20 ppb), spot LCM pill (50 bbl, 40 ppb)
Kick: Shut in well, circulate out using Driller's method, weight up mud as required
Stuck Pipe: Work pipe, spot pipe-free pill, jar down, back off if necessary
Wellbore Instability: Increase mud weight, add shale inhibitor, reduce trip speed

Emergency Contacts

Role	Name	Phone
Drilling Supervisor	Jason Bull	+64 21 555 0101
Toolpusher	Mike Thompson	+64 21 555 0102
Company Man	Sarah Williams	+64 21 555 0103
Medic	Dr. Emma Clarke	+64 21 555 0104
Helicopter	Kupe Air Ltd	+64 6 555 0105

Approvals

Role	Name	Signature	Date
Drilling Engineer	Jason Bull		30 Jan 2014
Operations Manager	Rachel Green		30 Jan 2014
Company Representative	Sarah Williams		30 Jan 2014

CONFIDENTIAL — This drilling program contains proprietary information. Unauthorized distribution is prohibited.

DAILY DRILLING REPORT

Well Name: Kupe 2H
Report Date: 31 Jan 2014
Report No.: 1
Rig: Ensign 970
Spud Date: 30 Jan 2014 06:00
Current Depth: 1,000.0 mMD / 999.5 mTVD
Progress: 1,000.0 m
Days Since Spud: 1.0

Operations Summary

Spudded well at 06:00 hrs. Drilled 17.5" surface hole from 120.0 mMD to 1,000.0 mMD. Circulated and conditioned mud. Ran and cemented 13.375" surface casing. Nipped up BOP and tested to 5,000 psi. Commenced drilling 12.25" intermediate hole.

From	To	Hrs	Activity	Code	Comments
06:00	08:30	2.5	Drilling	DRL	17.5" surface hole, 120.0 to 350.0 mMD
08:30	09:00	0.5	Survey	SVY	Gyro survey at 350.0 mMD
09:00	14:00	5.0	Drilling	DRL	17.5" surface hole, 350.0 to 650.0 mMD
14:00	14:30	0.5	Survey	SVY	Gyro survey at 650.0 mMD
14:30	18:00	3.5	Drilling	DRL	17.5" surface hole, 650.0 to 1,000.0 mMD
18:00	19:30	1.5	Circulate	CIRC	Circulate and condition mud for casing
19:30	22:00	2.5	Trip	TRP	POOH to run casing
22:00	00:30	2.5	Run Casing	RUN	Run 13.375" surface casing to 1,000.0 mMD
00:30	02:00	1.5	Cement	CMT	Cement 13.375" surface casing
02:00	04:00	2.0	Nipple Up	NU	Nipple up BOP and test to 5,000 psi
04:00	06:00	2.0	Drilling	DRL	12.25" intermediate hole, 1,000.0 to 1,050.0 mMD

Bit Record

Run	Size (in)	Type	Manufacturer	Model	Jets (32nds)	Depth In (mMD)	Depth Out (mMD)	Hours	ROP (m/hr)
1	17.5	PDC	Smith	MDSi613	3x20	120.0	1,000.0	18.5	51.4
2	12.25	PDC	Smith	MDSi616	3x18	1,000.0		2.0	25.0

Mud Properties

Time	Type	MW (ppg)	PV (cP)	YP (lbf/100ft²)	Gel 10s	Gel 10m	Gel 30m	FL (cc/30min)	pH	Solids (%)	Sand (%)	Chlorides (mg/L)
06:00	Spud Mud	8.6	15	20	5	8	10	12	9.0	4	0.5	500
14:00	Spud Mud	8.8	16	22	5	9	11	11	9.0	5	0.5	600
22:00	Spud Mud	9.0	17	24	6	9	11	10	9.0	5	0.5	800
06:00	KCl/Polymer	9.2	18	25	6	10	12	8	9.0	6	0.5	1,000

Survey Data

MD (mMD)	Inc (°)	Azi (°)	TVD (mTVD)	N/S (m)	E/W (m)	DLS (°/30m)
0.0	0.0	0.0	0.0	0.0	0.0	0.0
350.0	0.5	210.0	350.0	-1.5	-0.9	0.4
650.0	1.2	215.0	649.9	-5.8	-3.4	0.7
1,000.0	2.0	220.0	999.5	-14.2	-8.6	0.8

Personnel on Site

Role	Name	Company
Drilling Supervisor	Jason Bull	Kupe Energy
Toolpusher	Mike Thompson	Ensign
Company Man	Sarah Williams	Kupe Energy
Driller	Tom Harris	Ensign
Assistant Driller	Dave Wilson	Ensign
Mud Engineer	Lisa Chen	Halliburton
MWD Operator	Ryan Patel	Halliburton
Roustabout	James Cook	Ensign
Roustabout	Peter Adams	Ensign
Medic	Dr. Emma Clarke	Kupe Energy

Safety

Incidents: None
Near Misses: None
Safety Meeting: Held at 06:00 hrs. Topics: Working at height, PPE, Emergency muster points.

Weather

Conditions: Overcast, light rain
Wind: 15 kts SW
Temperature: 12°C

Forecast

Continue drilling 12.25" intermediate hole to 2,000.0 mMD. Run and cement 9.625" intermediate casing. Nipple up and test BOP. Commence drilling 8.5" production hole.

DAILY DRILLING REPORT

Well Name: Kupe 2H
Report Date: 1 Feb 2014
Report No.: 2
Rig: Ensign 970
Spud Date: 30 Jan 2014 06:00
Current Depth: 2,000.0 mMD / 1,999.0 mTVD
Progress: 1,000.0 m
Days Since Spud: 2.0

Operations Summary

Drilled 12.25" intermediate hole from 1,000.0 mMD to 2,000.0 mMD. Circulated and conditioned mud. Ran and cemented 9.625" intermediate casing. Nipped up BOP and tested to 5,000 psi. Commenced drilling 8.5" production hole.

From	To	Hrs	Activity	Code	Comments
06:00	12:00	6.0	Drilling	DRL	12.25" intermediate hole, 1,000.0 to 1,500.0 mMD
12:00	12:30	0.5	Survey	SVY	Gyro survey at 1,500.0 mMD
12:30	18:00	5.5	Drilling	DRL	12.25" intermediate hole, 1,500.0 to 2,000.0 mMD
18:00	20:00	2.0	Circulate	CIRC	Circulate and condition mud for casing
20:00	23:30	3.5	Trip	TRP	POOH to run casing
23:30	02:00	2.5	Run Casing	RUN	Run 9.625" intermediate casing to 2,000.0 mMD
02:00	03:30	1.5	Cement	CMT	Cement 9.625" intermediate casing
03:30	05:30	2.0	Nipple Up	NU	Nipple up BOP and test to 5,000 psi
05:30	06:00	0.5	Drilling	DRL	8.5" production hole, 2,000.0 to 2,010.0 mMD

Bit Record

Run	Size (in)	Type	Manufacturer	Model	Jets (32nds)	Depth In (mMD)	Depth Out (mMD)	Hours	ROP (m/hr)
1	17.5	PDC	Smith	MDSi613	3x20	120.0	1,000.0	18.5	51.4
2	12.25	PDC	Smith	MDSi616	3x18	1,000.0	2,000.0	22.0	45.5
3	8.5	PDC	Smith	MDSi619	3x16	2,000.0		0.5	20.0

Mud Properties

Time	Type	MW (ppg)	PV (cP)	YP (lbf/100ft²)	Gel 10s	Gel 10m	Gel 30m	FL (cc/30min)	pH	Solids (%)	Sand (%)	Chlorides (mg/L)
06:00	Spud Mud	9.2	18	25	6	10	12	8	9.0	6	0.5	1,000
12:00	KCl/Polymer	9.5	20	28	7	11	13	7	9.5	7	0.5	30,000
18:00	KCl/Polymer	9.8	22	30	8	12	15	6	9.5	8	0.5	35,000
06:00	KCl/Polymer	10.2	25	35	10	15	18	4	9.5	10	0.5	40,000

Survey Data

MD (mMD)	Inc (°)	Azi (°)	TVD (mTVD)	N/S (m)	E/W (m)	DLS (°/30m)
0.0	0.0	0.0	0.0	0.0	0.0	0.0
350.0	0.5	210.0	350.0	-1.5	-0.9	0.4
650.0	1.2	215.0	649.9	-5.8	-3.4	0.7
1,000.0	2.0	220.0	999.5	-14.2	-8.6	0.8
1,500.0	3.5	218.0	1,498.8	-38.6	-24.1	1.0
2,000.0	5.0	215.0	1,997.5	-72.4	-46.8	0.9

Personnel on Site

Role	Name	Company
Drilling Supervisor	Jason Bull	Kupe Energy
Toolpusher	Mike Thompson	Ensign
Company Man	Sarah Williams	Kupe Energy
Driller	Tom Harris	Ensign
Assistant Driller	Dave Wilson	Ensign
Mud Engineer	Lisa Chen	Halliburton
MWD Operator	Ryan Patel	Halliburton
Roustabout	James Cook	Ensign
Roustabout	Peter Adams	Ensign
Medic	Dr. Emma Clarke	Kupe Energy

Safety

Incidents: None
Near Misses: None
Safety Meeting: Held at 06:00 hrs. Topics: Working at height, PPE, Emergency muster points.

Weather

Conditions: Overcast, light rain
Wind: 15 kts SW
Temperature: 12°C

Forecast

Continue drilling 8.5" production hole to 3,000.0 mMD. Run and cement 5.5" production casing. Nipple up and test BOP. Commence completion operations.

DAILY DRILLING REPORT

Well Name: Kupe 2H
Report Date: 2 Feb 2014
Report No.: 3
Rig: Ensign 970
Spud Date: 30 Jan 2014 06:00
Current Depth: 3,000.0 mMD / 2,999.0 mTVD
Progress: 1,000.0 m
Days Since Spud: 3.0

Operations Summary

Drilled 8.5" production hole from 2,000.0 mMD to 3,000.0 mMD. Circulated and conditioned mud. Ran and cemented 5.5" production casing. Nipped up BOP and tested to 5,000 psi. Commenced completion operations.

From	To	Hrs	Activity	Code	Comments
06:00	12:00	6.0	Drilling	DRL	8.5" production hole, 2,000.0 to 2,500.0 mMD
12:00	12:30	0.5	Survey	SVY	Gyro survey at 2,500.0 mMD
12:30	18:00	5.5	Drilling	DRL	8.5" production hole, 2,500.0 to 3,000.0 mMD
18:00	20:00	2.0	Circulate	CIRC	Circulate and condition mud for casing
20:00	23:30	3.5	Trip	TRP	POOH to run casing
23:30	02:00	2.5	Run Casing	RUN	Run 5.5" production casing to 3,000.0 mMD
02:00	03:30	1.5	Cement	CMT	Cement 5.5" production casing
03:30	05:30	2.0	Nipple Up	NU	Nipple up BOP and test to 5,000 psi
05:30	06:00	0.5	Completion	COMP	Commence completion operations

Bit Record

Run	Size (in)	Type	Manufacturer	Model	Jets (32nds)	Depth In (mMD)	Depth Out (mMD)	Hours	ROP (m/hr)
1	17.5	PDC	Smith	MDSi613	3x20	120.0	1,000.0	18.5	51.4
2	12.25	PDC	Smith	MDSi616	3x18	1,000.0	2,000.0	22.0	45.5
3	8.5	PDC	Smith	MDSi619	3x16	2,000.0	3,000.0	30.0	33.3

Mud Properties

Time	Type	MW (ppg)	PV (cP)	YP (lbf/100ft²)	Gel 10s	Gel 10m	Gel 30m	FL (cc/30min)	pH	Solids (%)	Sand (%)	Chlorides (mg/L)
06:00	KCl/Polymer	9.8	22	30	8	12	15	6	9.5	8	0.5	35,000
12:00	KCl/Polymer	10.0	24	33	9	14	17	5	9.5	9	0.5	38,000
18:00	KCl/Polymer	10.2	25	35	10	15	18	4	9.5	10	0.5	40,000

Survey Data

MD (mMD)	Inc (°)	Azi (°)	TVD (mTVD)	N/S (m)	E/W (m)	DLS (°/30m)
0.0	0.0	0.0	0.0	0.0	0.0	0.0
350.0	0.5	210.0	350.0	-1.5	-0.9	0.4
650.0	1.2	215.0	649.9	-5.8	-3.4	0.7
1,000.0	2.0	220.0	999.5	-14.2	-8.6	0.8
1,500.0	3.5	218.0	1,498.8	-38.6	-24.1	1.0
2,000.0	5.0	215.0	1,997.5	-72.4	-46.8	0.9
2,500.0	6.5	212.0	2,496.0	-115.2	-74.5	0.9
3,000.0	8.0	210.0	2,994.0	-167.5	-107.3	0.8

Personnel on Site

Role	Name	Company
Drilling Supervisor	Jason Bull	Kupe Energy
Toolpusher	Mike Thompson	Ensign
Company Man	Sarah Williams	Kupe Energy
Driller	Tom Harris	Ensign
Assistant Driller	Dave Wilson	Ensign
Mud Engineer	Lisa Chen	Halliburton
MWD Operator	Ryan Patel	Halliburton
Roustabout	James Cook	Ensign
Roustabout	Peter Adams	Ensign
Medic	Dr. Emma Clarke	Kupe Energy

Safety

Incidents: None
Near Misses: None
Safety Meeting: Held at 06:00 hrs. Topics: Working at height, PPE, Emergency muster points.

Weather

Conditions: Overcast, light rain
Wind: 15 kts SW
Temperature: 12°C

Forecast

Continue completion operations. Run tubing and packer. Perforate production zone. Flow test well.


6700
6750
6800
6850
6900
6950
7000
7050
7100
7150
FLAG
7200
7250
7300
7350
7400
7450
FLAG
7500
7550
7600
9
Collar Locator
-1
0
Gamma Ray (GAPI)
270
0
Amplified Amplitude (mV)
30
0
Amplitude (mV)
200
85
VDL
1200