

Geologist Information

General: New location, 17 new wells (9 drilled first)
Ownership: FED surface/ Fed minerals
SUA Status: NA
Spacing Units: 1 unit – RG Unit
Adjacent Owners: BLM

1S 98W

25

CR 63

16"

8"



0 75 150 300 Feet

Plan of Development

Access: Use new access as shown on map
Drilling: Efficiency rig
Cuttings: In pit on location
SIMOPS: No for first visit; TBD on 2nd visit
Completion: Frac on pad; if SIMOPS, frac pad is located on drilling pad
Flowback: On pad
Prod Equip: Production equipment to be on NE corner of pad
Pipeline: New 8" gas and 2-4" water lines will be buried in access road to pad as shown on map.
Comments: In year-round drilling area

Legend

- - - Proposed Pipeline
- Existing Pipeline
- - - Proposed Road
- Proposed Production Equipment Area
- Proposed Daylight Line
- Proposed Pad or Pit
- Proposed Culvert (18" Corrugated Metal)
- Road (from Rio Blanco County)

Williams Production RMT

RGU 32-25-198 Plan of Development

Date Prepared: February 28, 2011

