



410 17th Street, Suite 1500
Denver, CO 80202
(720) 440-6100 phone
(720) 305-0804 fax

Bonanzaacrk.com

BMPs for Pad Construction In a Sensitive Area: North Platte 14-34, North Platte 24-34 and associated production facility locations:

- 1) Prior to initiating construction work on locations subject to USACE Nationwide Permit No. 18., the location will be clearly delineated by Professional Land Surveyor contracted by either Bonanza or their wetlands consultant.
- 2) Sediment Erosion controls including, but not limited to silt fencing and waddles will be placed to prevent fill from entering jurisdictional waterways identified as part of the Section 404 permitting process.
- 3) Trenches for silt fences will be constructed at a distance from the waterways which will ensure that spoils or cuttings are not spilled into the waterway.
- 4) Following installation of the silt fence, soil cuttings will be shoveled by hand into the interior side of the erosion controls.
- 5) Appropriate sized culverts will be installed in Wetland Areas pre-determined to be filled, in order to allow for undisturbed flow of the jurisdictional waters, during times of waterflow.
- 6) Erosion controls will be inspected, and maintained in good functioning condition until interim reclamation is completed.