

BMP

<u>Type</u>	<u>Comment</u>
Wildlife	Powerlines will be designed to minimize raptor electrocutions by incorporating designs to minimize risks. The cutting pit will be fenced with 32" high woven wire to protect wildlife and domestic animals. Netting will be installed to prevent access by migratory birds.
Drilling/Completion Operations	A closed loop system will be implemented during drilling, using a cuttings catch pit, dewatering system, centrifuge system. Any skim oil will be truck to Chevron Main Water Plant (4 miles) and pipelined to an oil gathering collection station.
Construction	Chevron will ensure 110 percent secondary containment for any volume of fluids contained at the well site during the drilling and completion operations, including construction of a berm or diversion dike, collection trench, and the use of site grading to protect the nearby drainage wash.
Interim Reclamation	Any moisture content of the drill cuttings pit will be de-watered and at the time of closure the drill cuttings will meet the standards in table 910-1. The disturbed area not needed for well operation will be revegetated after the site has been properly prepared - recontouring the area to blend with surrounding topography. Broadcast certified seed using seed blend recommended by BLM, in fall (Sept 2011) seeding prior to prolonged ground frost.
Storm Water/Erosion Control	Top soil salvage and storage. Top soil will be stockpiled where no vehicle traffic will cross the mound. The stock piles will be protected from the wind and water erosion through the use of suitable weed free mulch and seeding.
Site Specific	This well site was selected to utilize one location for 2 directionally drilled wells, this location is located along an existing lease road. These two production wells will have two flowlines (using only one trench) to a centralized production facility offsite, no large haul trucks will be needed to collect produced fluids. There will be no holding tanks on this location.
Pre-Construction	The cuttings pit will be constructed to the BLM Gold Book standards. No portion of the drilling pit will be constructed on any fill material, the entire base of the pit will be in the cut.
Planning	Chevron trains all employees in safe work practices, good environmental stewardship, health and wellness issues and to ensure that proper personal protective equipment is available and is being used. Chevron has a up to date Spill Protection Control and Countermeasure Plan for the Rangely Field. Chevron has a zero tolerance policy regarding drug usage, with education and compliance programs to help reinforce these policies.
General Housekeeping	Any waste products will be handled by RN Industries, trash will be confined in a covered container. After the rig is off the location the well site will be cleaned and all refuse removed by Rangely Trash Service, and hauled to the approved landfill in Rio Blanco County. A portable toilet will be supplied for human waste.