


Approval

Signed: _____



Title: _____

Director of Cogcc

Date: _____

11/28/2012

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Site Specific	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.
Material Handling and Spill Prevention	Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit/Pond.
Site Specific	Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.
Planning	A Form 15 Pit Report will be submitted within 30 days of construction of the fresh water storage pit.
Site Specific	Operator will participate in the Colorado Oil & Gas Association Voluntary Baseline Groundwater Quality Sampling Program. Operator will implement interim reclamation measures immediately after construction of the location to stabilize cut and fill slopes, stabilize the topsoil and spoil stockpiles, establish desirable vegetation and control weeds on the location.

Total: 9 comment(s)

CONDITIONS OF APPROVAL:

Pit shall be constructed in accordance with "Civil Plans for WEP 27A & WEP 28A Well Pads & Freshwater Storage Pit #1 (FWSP#1)" dated November 2012 and certified by a Colorado Licensed Professional Engineer. Construction shall also conform to City of Aurora requirements and Colorado Department of Public Health and Environment Colorado Discharge Permit System (CDPS) requirements.

Pit liner shall be a minimum of 24 mil and shall be installed in accordance with manufacturer's specifications.