

# HSR Fairfax 16-8 05-123-15679 - Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

3-7/8" Deepened Liner

## Existing

KB: 4907  
GL: 4896

8 5/8" Surf Csg Shoe @ 468  
Base Fox Hills @ Behind Pipe

Top of Sussex @ 4312  
Base of Shannon @ 5632

TOC @ 6700

NB Top @ 7099

NB perms @ 7104-7275  
CD perms @ 7390-7406

4 1/2" Prod Csg @ 7543

JS perms @ 7836-7905  
Deepened Liner @ 8026  
TD @ 8026

## Planned

30 sx of cement

Welded Cap  
Surface plug 10'-100'  
CIBP @ 100

150 sx of cement  
cement plug from 650'-100'  
Cut Casing @ 600

Squeeze holes @ 4080  
CICR @ 4110  
Squeeze holes @ 5830

850 sx of cement

Balanced Plug in 4-1/2" csg @ 6700'

25 sx of cement

CIBP @ 7040' w/ min 2 sx cement

CIBP @ 7740' w/ min 2 sx cement

