

HSR Federal 14-36 05-123-18482 - Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

Existing

KB: 5013
GL: 5003

Base Fox Hills @ Behind Pipe
8 5/8" Surf Csg Shoe @ 764

Top of Sussex @ 4465
Base of Shannon @ 5278

TOC @ 6315

NB Top @ 7123

NB perfs @ 7178-7182
CD perfs @ 7402-7412

3 1/2" Prod Csg @ 7542
TD @ 7595

Planned

25 sx of cement

Welded Cap
Surface plug 10'-100'
CIBP @ 100

90 sx 0.0155 bbl/Inft PC, 9.5" caliper &
20% excess, 0.0636 bbl/Inft SC

Stub plug @ 970-560
cut csg @ 870

Squeeze holes @ 4235
CICR @ 4265
Squeeze holes @ 5480

550 sx of neat G, 9"
caliper & 40% excess

20 sx of neat G, 0.00914 bbl/Inft

Balanced cmnt plug @ 6720'-7110'

CIBP @ 7110'

	Mud
	Existing Cement
	New Cement