

Pronghorn Operating LLC
8400 East Prentice Ave, Suite 1000
Greenwood Village, CO 80111

RE: Mull-UPRC-Hanavan #1 Re-Entry Drilling Plan

1. Excavate existing 13 3/8" casing stub, weld on extension with 13 3/8" flange. Excavate and level location, dig drilling pit
2. MIRU Drilling Rig
3. MU 7-7/8" bit and drilling assembly
4. Drill out abandonment cement plugs to 2785', clean out old hole to original TD of 5503'
5. Run 5 1/2" casing from surface to approximately 5500' with port collar at sufficient depth to satisfy upper stage cement as determined by the approved permit
6. Cement in place with 150 sx 1.42 yield Class A OWC
7. RDMO Drilling Rig
8. Log cement bond log, perforate and test the Mississippian formation
9. Pending results hook up as a commercial well or with abandonment operations per the approved permit