

GENERAL WELL INFORMATION

Well Name	Wells Ranch USX AA13-08
Target Formation	Parkman
Location	Sec 13, T6N, R63W
Foreman Area	N5
WI/NRI (%)	100/80
Land Use	Anytime
Net PDP (MBOE)	8.547
Net PDNP (MBOE)	0.000
Current Gas Rate (MCFD)*	0.1
Current Oil Rate (BOPD)*	0.2
Execution Date	September 2013

EXECUTION PROCEDURE

1. MIRU workover rig. Top kill well in 10 bbl increments with clean 2% KCl.
2. ND WH, NU BOP. POOH with all 2 3/8" tbg landed @6754 ft.
3. RIH with bit scraper and 2 3/8" tbg. Tag TD and clean out to 3716 ft if necessary. POOH.
4. RIH with CIBP and set @3716 ft (100 ft below targeted Parkman interval). Pressure test csg to 3000 psi.
5. Swab the well down and perf under balanced from 3610 ft – 3616 ft with 3 1/8" slick gun with 4 spf, 20 gram charges, 0.73" entry holes, 8" penetration, 60 degree phasing.
6. Swab well until oil is seen and flowtest well. Contact Denver Engineering.