

Wording for Regulatory Agency filing:

"Chevron USA Inc. is pleased to provide a courtesy notification of a proposed change in the well equipment on the following well pads: Wheeler 13-2, Wheeler 13-4, IC Wheeler 12U-1, IC SU 12U-2, and IC Wheeler 12U-4. A buried 2" carbon steel dual flow line will be installed from the well-head to the separator cabinet on each of these wells to enhance production. A 95bbl above-ground carbon steel tank (3'h x 15'dia) will also be installed to provide proper containment of any liquids that potentially may vent from the pressure relief valve on the new dual flow line. All work for all of the sites listed will be done on the well pad itself. There will not be any new ground disturbance."

Per the La Plata County GIS website (link below), here are the distances to the closest water wells for each of the WAIC DFL locations:

Indian Creek Wheeler 13-2	2: 0.25 miles (permit #154179-)
Indian Creek Wheeler 13-4	437.5 feet (Permit #209132--)
Indian Creek SU 12U-1	0.39 miles (permit #209132--)
Indian Creek SU 12U-2	0.65 miles (permit #53789-F-)
Indian Creek SU 12U-4	0.27 miles (permit #53789-F-)