



Project: RG 26-01S-098W  
Site: RGU 11-26-198  
Well: RGU 21-26-198  
Design #2 05Nov13 kjs

T

M

Azimuths to True North  
Magnetic North: 10.31°  
Magnetic Field  
Strength: 52229.0snT  
Dip Angle: 65.98°  
Date: 7/9/2013  
Model: IGRF2010

ANNOTATIONS								
TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
120.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 3.00
349.44	350.00	6.90	82.55	1.79	13.72	13.83	13.83	Hold 6.90 Inclination
3500.00	3523.54	6.90	82.55	51.23	391.76	395.09	395.09	Start Build 3.00
4021.77	4065.61	23.16	82.55	69.40	530.69	535.20	535.20	Hold 23.16 Inclination
6415.18	6668.85	23.16	82.55	202.20	1545.98	1559.15	1559.15	Start Drop -2.00
7542.00	7826.96	0.00	0.00	232.15	1774.95	1790.07	1790.07	Vertical
7642.00	7926.96	0.00	0.00	232.15	1774.95	1790.07	1790.07	Mesaverde
12447.00	12731.96	0.00	0.00	232.15	1774.95	1790.07	1790.07	TD at 12731.96