



Project: RG 26-01S-098W

Site: RGU 11-26-198

Well: RGU 42-27-198

Design #2 05Nov13 kjs

T

M

Azimuths to True North

Magnetic North: 10.31°

Magnetic Field

Strength: 52229.0snT

Dip Angle: 65.98°

Date: 7/9/2013

Model: IGRF2010

ANNOTATIONS									
TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation	
120.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 3.00	
286.46	286.67	5.00	218.09	-5.72	-4.48	7.27	7.27	Hold 5.00 Inclination	
3500.00	3512.49	5.00	218.09	-227.00	-177.92	288.42	288.42	Start Build 3.00	
3845.54	3864.15	15.55	218.09	-276.29	-216.57	351.05	351.05	Hold 15.55 Inclination	
6574.01	6696.29	15.55	218.09	-873.81	-684.98	1110.29	1110.29	Start Drop -2.00	
7342.00	7473.79	0.00	0.00	-956.33	-749.68	1215.15	1215.15	Vertical	
7442.00	7573.79	0.00	0.00	-956.33	-749.68	1215.15	1215.15	Mesaverde	
12182.00	12313.79	0.00	0.00	-956.33	-749.68	1215.15	1215.15	TD at 12313.79	