


Project: RG 26-01S-098W
Site: RGU 11-26-198
Well: RGU 621-26-198
Design #2 05Nov13 kjs



Azimuths to True North
Magnetic North: 10.31°
Magnetic Field
Strength: 52229.0snT
Dip Angle: 65.98°
Date: 7/9/2013
Model: IGRF2010

ANNOTATIONS								
TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
120.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 3.50
316.67	317.14	6.90	72.73	3.52	11.32	11.86	11.86	Hold 6.90 Inclination
3500.00	3523.70	6.90	72.73	117.88	379.18	397.08	397.08	Start Build 3.50
3970.78	4014.03	24.06	72.72	156.61	503.68	527.47	527.47	Hold 24.06 Inclination
6383.97	6656.87	24.06	72.72	476.66	1532.59	1605.00	1605.00	Start Drop -2.00
7552.00	7859.95	0.00	0.00	550.60	1770.28	1853.93	1853.93	Vertical
7652.00	7959.95	0.00	0.00	550.60	1770.28	1853.93	1853.93	Mesaverde
12462.00	12769.95	0.00	0.00	550.60	1770.28	1853.93	1853.93	TD at 12769.95