



Project: TR 28-05S-097W

Site: TR 24-28-597 Pad

Well: TR 414-28-597

Plan #5 12Aug13 kjs

T

M

Azimuths to True North

Magnetic North: 10.88°

Magnetic Field

Strength: 52579.5snT

Dip Angle: 65.85°

Date: 4/14/2008

Model: IGRF200510

ANNOTATIONS									
MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation		
120.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 2.00		
994.24	17.77	251.79	-42.70	-129.81	136.65	136.65	Hold 17.77 Inclination		
4756.30	17.77	251.79	-400.13	-1216.25	1280.38	1280.38	Start Drop -1.50		
5940.84	0.00	0.00	-457.07	-1389.33	1462.59	1462.59	Vertical		
6040.84	0.00	0.00	-457.07	-1389.33	1462.59	1462.59	Mesaverde		
9564.84	0.00	0.00	-457.07	-1389.33	1462.59	1462.59	TD at 9564.84		