



ESTIMATED EARTHWORK QUANTITIES (cy)

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	10810	10620	2940	-2750
PIT	6000			6000
TOTALS	16810	10620	2940	3250

- *NOTE:
- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
 - 2.) Topsoil Volume Based on 12" Soil Depth.
 - 3.) Total Disturbed Area = ±4.82 ac.
 - 4.) Access Road Earthwork Volume Included in Table.(3090 cy Fill).
 - 5.) Use Pit Excavation to Complete Pad.

REVISED: 6/17/14

136 East Third Street
Rifle, Colorado 81650
Ph. (970) 625-2720
Fax (970) 625-2773

BOOKCLIFF
Survey Services, Inc.

SCALE:	1" = 80'
DATE:	6/6/14
PLAT:	2 of 7
PROJECT:	Valley
DFT:	cs

Construction Plan Prepared for:
WPXENERGY WPX Energy Rocky Mountain, LLC

RMV 20-35 Drill Pad - Plat 2
Facility Drawing Layout