

Section 28  
T. 6 S., R. 96 W.

Toe Trench  
(RC-14)

Temporary  
Berm  
(RC-08)

Sediment Trap  
(SC-06)

move tanks and  
separators off pad  
along toe of fill, on  
their own pad and  
add cuts/fills.

#### QUANTITIES (cy)

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	10480	5250	1640	3590
PIT	5000			5000
TOTALS	15480	5250	1640	8590

#### \*NOTE:

- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 2.) Topsoil Volume Based on 12" Soil Depth.
- 3.) Total Disturbed Area = ±4.81 ac

136 East Third Street  
Rifle, Colorado 81650  
Ph. (970) 625-2720  
Fax (970) 625-2773



**BOOKCLIFF**  
Survey Services, Inc.

SCALE: 1" = 80'  
DATE: 6/13/14  
PLAT: 2 of 7  
PROJECT: Valley  
DFT: CS

Construction Plan Prepared for:  
**WPX ENERGY**

WPX Energy Rocky Mountain, LLC

GV 26-28 - Plat 2  
Construction SW BMP's