



#### ESTIMATED EARTHWORK QUANTITIES (cy)

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	6010	3270	2380	360
PIT	0			0
TOTALS	5750	3270	2380	360

#### \*NOTE:

- 1.) Topsoil Volume Based on 12" Soil Depth.
- 2.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 3.) Total Disturbed Area = ±3.20 ac.

REVISED: 8/29/14 volumes

136 East Third Street  
Rifle, Colorado 81650  
Ph. (970) 625-2720  
Fax (970) 625-2773



**BOOKCLIFF**  
Survey Services, Inc.

SCALE: 1" = 80'  
DATE: 8/7/14  
PLAT: 1 of 5  
PROJECT: Valley  
DFT: cs



WPX Energy Rocky Mountain, LLC

RU 14-6 Frac. Pad - Plat 1  
CONSTRUCTION LAYOUT