



**LEGEND:**

- (WT) PROPOSED WATER TANK
- (NS) PROPOSED SEPARATOR
- (FO) PROPOSED FLARE STACK
- (HT) PROPOSED HEATER TREATERS
- (C) PROPOSED COMPRESSOR
- (VO) PROPOSED VOC COMBUSTOR

EXISTING ELEVATION AT WELL HEAD=4,927.1'  
 PROPOSED ELEVATION AT WELL HEAD=4,927.3'  
 EARTHWORK QUANTITY SUMMARY:  
 TOPSOIL VOLUME: 3629.6 CY  
 CUT VOLUME: 17,376.6 CY  
 FILL VOLUME: 14,070.7 CY

NOTE: NO SHRINK/SWELL FACTORS HAVE BEEN APPLIED TO THE ABOVE QUANTITIES. THE PAD WAS DESIGNED SUCH THAT THE CUT QUANTITY IS AT LEAST 20% MORE THAN THE FILL QUANTITY.

