

Pronghorn Operating LLC  
8400 East Prentice Ave, Suite 1000  
Greenwood Village, CO 80111

**RE: Morton Trust 32-32 2 Re-Entry Drilling Plan**

1. Excavate existing 8 5/8" casing stub, weld on extension with 8 5/8" flange. Excavate and level location, dig drilling pit
2. MIRU Drilling Rig
3. MU 7-7/8" bit and drilling assembly
4. Drill out abandonment cement plugs & clean out old hole to original TD of 5410'
5. Run 5 1/2" casing from surface to approximately 5410' with port collar at sufficient depth to satisfy upper stage cement as determined by the approved permit
6. Cement in place with 150 sx 1.42 yield Class A OWC
7. RDMO Drilling Rig
8. Log cement bond log, perforate and test the Mississippian formation
9. Pending results hook up as a commercial well or with abandonment operations per the approved permit