


| ESTIMATED EARTHWORK QUANTITIES (cy) |       |      |         |        |
|-------------------------------------|-------|------|---------|--------|
| ITEM                                | CUT   | FILL | TOPSOIL | EXCESS |
| PAD                                 | 10330 | 2120 | 3480    | 4730   |
| PIT                                 | 16100 |      |         | 16100  |
| TOTALS                              | 26430 | 2120 | 3480    | 20830  |

\*NOTE:

- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 2.) Topsoil Volume Based on 12" Soil Depth.
- 3.) Total Disturbed Area =  $\pm 6.51$  ac.

|  |
|--|
| <b>Construction Plan Prepared for:</b><br> <b>WPX Energy Rocky Mountain, LLC</b>                |
| <i>PA 24-32 Drill Pad - Plat 2</i><br><div style="border: 2px solid red; padding: 5px; display: inline-block; color: red; font-weight: bold;"> <b>Facility Layout Drawing</b> </div> |