



Exploration and Production

Water Isolation Procedure

Wellname: **RWF 332-25**
Location: **SENE 25 6S 94W**
Field: **South Rulison**
API: **05-045-14829**

Prepared By: Mackenzie Johnston
Cell Phone: (970) 640-5904

Revision Date:
5/20/2015

Surface Casing: 9-5/8" 32.3# set @ 2446.7-ft
Production Casing: 4-1/2" 11.6# set @ 8806.5-ft
Tubing: 2-3/8" tbg @ 6329.5-ft
MV Completions: 6136-7831 ft
Cameo Completions: 7871-8507-ft
TOC/Correlate Logs: 4402-ft / Halliburton CBL 3/20/2008

Purpose: Return bottom perms to production

Proposed Procedure:

- 1 MIRU service rig, POOH w/ 2-3/8" tbg
- 2 PU pump off bit
- 3 RIH and drill CIBP at 6696'
- 4 Land tubing .
- 5 POOH and RD wireline
- 7 RD rig and MO
- 8 Swab well.
- 9 Submit subsequent report

