




Lat40°, Inc. 6250 W. 10th Street, Unit 2, Greeley, CO 970-515-5294

# WELL LOCATION CERTIFICATE

R&R FARMS 29L-241

THIS MAP DOES NOT REPRESENT A BOUNDARY SURVEY

SECTION: 29  
TOWNSHIP: 5N  
RANGE: 63W



In accordance with a request from Jeff Dillingham with PDC ENERGY, INC. Lat40°, Inc. has determined the surface location of the R&R FARMS 29L-241 to be 641' from the SOUTH line and 374' from the WEST line and the bottom hole to be 500' from the NORTH line and 738' from the WEST line as measured at right angles from the section lines of Section 29, Township 5 North, Range 63 West of the Sixth Principal Meridian, County of Weld, State of Colorado.

I hereby state that this Well Location Certificate was prepared by me, or under my direct supervision, that the fieldwork was completed on 3/16/2015, for and on behalf of PDC ENERGY, INC. That this is not a Land Survey Plat or an Improvement Survey Plat, and that it is not to be relied upon for establishment of fence, building, or other future improvement lines.

NOTE:

- 1) Bearings shown are Grid Bearings of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983. The lined dimensions as contained herein are based upon the "U.S. Survey Foot."
- 2) Ground elevations are based on an observed GPS elevation (NAVD 1988 DATUM).
- 3) IMPROVEMENTS: See LOCATION DRAWING for all visible improvements within 500' of oil and gas location.
- 4) SURFACE USE: CROP LAND
- 5) INSTRUMENT OPERATOR: BRIAN ROTTINGHAUS
- 6) NEAREST CULTURAL ITEMS:  
BUILDING: ±313' SW  
BUILDING UNIT: ±417' SW  
HIGH OCCUPANCY BUILDING UNIT: +5280'  
DESIGNATED OUTSIDE ACTIVITY AREA: +5280'  
PUBLIC ROAD: ±361' W (CR 63)  
ABOVEGROUND UTILITY: ±404' W  
RAILROAD: +5280'  
PROPERTY LINE: ±374' W

SURFACE LOCATION

LAT: 40.36504°N  
LONG: 104.46827°W  
PDOP: 1.9  
ELEV: 4574'  
1/4, 1/4: SWSW

BOTTOM HOLE

LAT: 40.37634°N  
LONG: 104.46709°W


ENTRY POINT

LAT: 40.36552°N  
LONG: 104.46710°W

LEGEND

- = ALIQUOT MONUMENT AS DESCRIBED
- = CALCULATED POSITION

Brian T. Brinkman—On behalf of Lat40° Inc.  
Colorado Licensed Professional Surveyor No. 38175  
DATE: 04/21/2015  
PROJECT#: 2014131







# SITE SKETCH

## R&R FARMS 29L-241

SECTION: 29  
TOWNSHIP: 5N  
RANGE: 63W



WELL NO.	WELL NAME	SHL FOOTAGE			SHL LAT°	SHL LONG°	PDOP	ELEV (FT.)	1/4/1/4	
		FSL	2007	FWL						
9	ROTHER 24-29U	649	FSL	2007	FWL	40.36506	-104.46241	2.2	4573	SESW
10	ROTHER 29BU	1210	FSL	1396	FWL	40.36660	-104.46462	1.7	4565	SESW
11	ROTHER 14-29U	642	FSL	666	FWL	40.36504	-104.46723	1.8	4572	SWSW
12	ROTHER 13-29U	1930	FSL	676	FWL	40.36858	-104.46723	1.7	4568	NWSW
17	ROTHER 23-29U	1948	FSL	2112	FWL	40.36862	-104.46207	1.7	4566	NESW