

Procedure to add additional Wasatch perforations and fracture stimulate the Duncan B 14 well in the Hiawatha Field. Moffat County, Colorado.

- MIRU Service Unit. Install BOPs and test'
- TOH with tubing.
- Cleanout fill to PBTD at 5220'
- Set CIBP @ 3000'
- Perforate casing at 2768-2792'. Wasatch 9
- Frac perforated intervals.
- Perforate casing at 2463-2479'. Wasatch 11
- Frac perforated intervals
- Cleanout to PBTD at 5220'
- Run 2-3/8" production tubing
- RDMOSU and clean location
- Return well to producing.