

## **Laramie Energy/Piceance Energy Harrison Creek Water Treatment Facility (HCWTF)**

### **Impoundment Fluid Transfer Protocols and Contingency Plan**

- 1) All fluid transfers from the Dissolved Air Flootation (DAF) Facility to the impoundments will be overseen by the onsite manager.
- 2) Fluid transfer volumes into the DAF facility will monitored and recorded at all times.
- 3) Fluid transfer volumes from the DAF facility to the impoundments will monitored and recorded at all times.
- 4) Records of fluid transfers will be stored onsite at the HCWTF.

#### **Fluid Transfer Protocols**

- Coordinate with onsite manager regarding anticipated timing and approximate volumes of fluid transfer.
- Confirm leak detection system is operating properly.
- After fluid transfer is complete, record or gather fluid transfer volume data.

#### **Fluid Transfer Contingency Plan**

- In the event of a leak detection alarm, contact the DAF onsite manager immediately.
- Record date and time of event.
- Coordinate with the DAF onsite manager to terminate fluid transfer.
- Confirm fluid transfer to the impoundment has been terminated at the impoundment inflow location.
- Coordinate with the DAF onsite manager to draw down impoundment until fluid is no longer accumulating in the leak detection sump.
- Pump fluids from leak detection sump and record fluid volumes.
- Collect 3 (three) water samples of fluid from the sump for analysis.
- Report event to the appropriate regulatory authorities (COGCC, etc.) and local government representative(s).
- Investigate the source of fluid accumulation in the sump/leak detection system. Coordinate repairs as appropriate and test to determine if fluid accumulation has been stopped.
- Reset leak detection system and monitor for 72 hours to confirm fluid is no longer accumulating in the sump.
- Secure all available data related to fluid transfer volumes at the time of the alarm.