




LEGEND

●	WELL LOCATION
—○—	FENCE LINE
- - - - -	CONTAINMENT BERM
○	ABOVE GROUND STORAGE TANK
[]	FORMER FACILITY

Figure 1
SITE MAP

Noble Burke RG 24-8
Facility ID - 326831
SE NE Section 24, T4N, R65W
Weld County, Colorado

API No. 05-123-13732	Prepared by	Drawn by JMA	
Date 3/31/16	Reviewed by	Filename V006A	

Summit Scientific

741 Corporate Circle – Suite I ♦ Golden, Colorado 80401

303.277.9310 - laboratory ♦ 303.277.9531 - fax

January 21, 2016

Paul Henehan
Fremont Environmental
1759 Redwing Lane
Broomfield, CO 80020
RE: Noble - Burke RG 24-8

Enclosed are the results of analyses for samples received by Summit Scientific on 01/20/16 16:11. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

A handwritten signature in black ink, appearing to read 'P. Shrewsbury', with a stylized, cursive script.

Paul Shrewsbury
President



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
N. Wall 3 ft	1601154-01	Soil	01/20/16 00:00	01/20/16 16:11
Floor 6 Ft	1601154-02	Soil	01/20/16 00:00	01/20/16 16:11

Summit Scientific

A handwritten signature in black ink, appearing to be 'MSM'.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Summit Scientific

S₂

741 Corporate Circle, Suite J ♦ Golden, Colorado 80401
303-277-9310 ♦ 303-374-5933

1601155401

Page 1 of 1

Client: FREMONT/NOBLE Project Manager: HENEHAN
Address: _____ E-Mail: _____
City/State/Zip: _____
Phone: 303/9568714 Fax: _____ Project Name: NOBLE - DOW 1-29
Sampler Name: HENEHAN Project Number: _____

ID	Sample Description	Date Sampled	Time Sampled	# of containers	Preservative				Matrix				Analysis Requested						Special Instructions
					HCl	HNO ₃	None	Other (Specify)	Groundwater	Soil	Air-Canister #	Other (Specify)	BTEX	GRD/DRO	NAPHTH	SAR	EL	PH	
1	N. WALL 2 FT	1/20/16		1			✓		✓				✓	✓	✓	✓	✓		
2	FLOOR 3 FT	"		1			✓		✓				✓	✓	✓	✓			
3																			
4																			
5																			
6																			
7																			
8																			
9																			
10																			

Relinquished by: <u>PAUL HENEHAN</u>	Date/Time: <u>1/20/16 16:12</u>	Received by: <u>[Signature]</u>	Date/Time: <u>1-20-16 16:12</u>	Turn Around Time (Check) Same Day <input checked="" type="checkbox"/> 72 hours <input type="checkbox"/> 24 hours <input type="checkbox"/> Standard <input type="checkbox"/> 48 hours <input type="checkbox"/>	Notes:
Relinquished by: <u>[Signature]</u>	Date/Time: <u>1-20-16 18:15</u>	Received by: <u>[Signature]</u>	Date/Time: <u>1/20/16 18:15</u>	Sample Integrity: <u>THURS. AM RZ</u>	
Relinquished by: _____	Date/Time: _____	Received by: _____	Date/Time: _____	Temperature Upon Receipt: <u>16.2°C</u> Intact: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	

www.s2scientific.com

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

**N. Wall 3 ft
1601154-01 (Soil)**

Summit Scientific

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
C10-C28 (DRO)	ND	50	mg/kg	1	1601203	01/20/16	01/21/16	8015M	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: o-Terphenyl		92.8 %	30-150		"	"	"	"	

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Naphthalene	ND	0.010	mg/kg	1	1601202	01/20/16	01/20/16	EPA 8260B	
Benzene	ND	0.0020	"	"	"	"	"	"	
Toluene	ND	0.0050	"	"	"	"	"	"	
Ethylbenzene	ND	0.0050	"	"	"	"	"	"	
Xylenes (total)	ND	0.010	"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	50	"	"	"	"	"	"	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 1,2-Dichloroethane-d4		104 %	23-173		"	"	"	"	
Surrogate: Toluene-d8		98.9 %	20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		97.9 %	21-167		"	"	"	"	

Soluble Nutrients by EPA 6020/Mod. USDA60 6(2, 3A) - Dry Weight Basis

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

N. Wall 3 ft
1601154-01 (Soil)

Summit Scientific

Soluble Nutrients by EPA 6020/Mod. USDA60 6(2, 3A) - Dry Weight Basis

Analyte	Result	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	1190	11.4 mg/kg dry	1	1601201	01/20/16	01/20/16	EPA 6020/Mod. USDA60 6(2, 3A)	
Magnesium	439	5.69	"	"	"	"	"	
Sodium	723	5.69	"	"	"	"	"	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	4.55		units	"	1601204	01/21/16	01/21/16	"	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.152	0.0100	mmhos/cm	1	1601194	01/20/16	01/20/16	SM 2510B	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	6.03	0.100	pH Units	"	1601193	01/20/16	01/20/16	EPA 9045	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	87.8		%	"	1601195	01/20/16	01/21/16	% calculation	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Floor 6 Ft
1601154-02 (Soil)

Summit Scientific

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
C10-C28 (DRO)	ND	50	mg/kg	1	1601203	01/20/16	01/21/16	8015M	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: o-Terphenyl		99.6 %	30-150		"	"	"	"	

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Naphthalene	ND	0.010	mg/kg	1	1601202	01/20/16	01/20/16	EPA 8260B	
Benzene	ND	0.0020	"	"	"	"	"	"	
Toluene	ND	0.0050	"	"	"	"	"	"	
Ethylbenzene	ND	0.0050	"	"	"	"	"	"	
Xylenes (total)	ND	0.010	"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	50	"	"	"	"	"	"	

Date Sampled: 01/20/16 00:00

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 1,2-Dichloroethane-d4		104 %	23-173		"	"	"	"	
Surrogate: Toluene-d8		99.9 %	20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene		98.5 %	21-167		"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Extractable Petroleum Hydrocarbons by 8015 - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD	
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 1601203 - EPA 3550A

Blank (1601203-BLK1)

Prepared: 01/20/16 Analyzed: 01/21/16

C10-C28 (DRO) ND 50 mg/kg

Surrogate: o-Terphenyl 11.5 " 12.5 92.3 30-150

LCS (1601203-BS1)

Prepared: 01/20/16 Analyzed: 01/21/16

C10-C28 (DRO) 534 50 mg/kg 499 107 73-134

Surrogate: o-Terphenyl 11.7 " 12.5 93.3 30-150

Matrix Spike (1601203-MS1)

Source: 1601154-01

Prepared: 01/20/16 Analyzed: 01/21/16

C10-C28 (DRO) 569 50 mg/kg 485 15.7 114 50-148

Surrogate: o-Terphenyl 11.4 " 12.2 93.7 30-150

Matrix Spike Dup (1601203-MSD1)

Source: 1601154-01

Prepared: 01/20/16 Analyzed: 01/21/16

C10-C28 (DRO) 621 50 mg/kg 485 15.7 125 50-148 8.68 13

Surrogate: o-Terphenyl 12.3 " 12.2 101 30-150

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Volatile Organic Compounds by EPA Method 8260B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD	
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 1601202 - EPA 5030 Soil MS

Blank (1601202-BLK1)

Prepared: 01/20/16 Analyzed: 01/21/16

Naphthalene	ND	0.010	mg/kg							
Benzene	ND	0.0020	"							
Toluene	ND	0.0050	"							
Ethylbenzene	ND	0.0050	"							
Xylenes (total)	ND	0.010	"							
Gasoline Range Hydrocarbons	ND	50	"							
Surrogate: 1,2-Dichloroethane-d4	0.0411		"	0.0400		103	23-173			
Surrogate: Toluene-d8	0.0397		"	0.0400		99.2	20-170			
Surrogate: 4-Bromofluorobenzene	0.0402		"	0.0400		100	21-167			

LCS (1601202-BS1)

Prepared: 01/20/16 Analyzed: 01/21/16

Naphthalene	ND	0.010	mg/kg				66-138			
Benzene	0.113	0.0020	"	0.100		113	58-130			
Toluene	0.120	0.0050	"	0.100		120	61-134			
Ethylbenzene	0.130	0.0050	"	0.0992		131	74-139			
m,p-Xylene	0.244	0.010	"	0.200		122	73-137			
o-Xylene	0.118	0.0050	"	0.0984		120	73-141			
Surrogate: 1,2-Dichloroethane-d4	0.0401		"	0.0400		100	23-173			
Surrogate: Toluene-d8	0.0401		"	0.0400		100	20-170			
Surrogate: 4-Bromofluorobenzene	0.0400		"	0.0400		99.9	21-167			

Matrix Spike (1601202-MS1)

Source: 1601154-01

Prepared: 01/20/16 Analyzed: 01/21/16

Naphthalene	ND	0.010	mg/kg		ND		10-158			
Benzene	0.115	0.0020	"	0.0984	ND	117	30-131			
Toluene	0.122	0.0050	"	0.0984	ND	124	30-134			
Ethylbenzene	0.135	0.0050	"	0.0976	ND	138	22-153			
m,p-Xylene	0.254	0.010	"	0.196	ND	129	10-159			
o-Xylene	0.123	0.0050	"	0.0969	ND	127	31-151			
Surrogate: 1,2-Dichloroethane-d4	0.0405		"	0.0394		103	23-173			
Surrogate: Toluene-d8	0.0388		"	0.0394		98.6	20-170			
Surrogate: 4-Bromofluorobenzene	0.0396		"	0.0394		101	21-167			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Volatile Organic Compounds by EPA Method 8260B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD	
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 1601202 - EPA 5030 Soil MS

Matrix Spike Dup (1601202-MSD1)		Source: 1601154-01			Prepared: 01/20/16		Analyzed: 01/21/16			
Naphthalene	ND	0.010	mg/kg		ND		10-158			42
Benzene	0.115	0.0020	"	0.0958	ND	120	30-131	0.490		34
Toluene	0.123	0.0050	"	0.0958	ND	128	30-134	0.446		30
Ethylbenzene	0.134	0.0050	"	0.0950	ND	141	22-153	1.18		24
m,p-Xylene	0.249	0.010	"	0.191	ND	130	10-159	2.29		68
o-Xylene	0.123	0.0050	"	0.0943	ND	130	31-151	0.372		38
Surrogate: 1,2-Dichloroethane-d4	0.0403		"	0.0383		105	23-173			
Surrogate: Toluene-d8	0.0386		"	0.0383		101	20-170			
Surrogate: 4-Bromofluorobenzene	0.0386		"	0.0383		101	21-167			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Soluble Nutrients by EPA 6020/Mod. USDA60 6(2, 3A) - Dry Weight Basis - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD	
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 1601201 - General Preparation

Blank (1601201-BLK1)

Prepared & Analyzed: 01/20/16

Calcium	ND	10.0	mg/kg wet
Magnesium	ND	5.00	"
Sodium	ND	5.00	"

LCS (1601201-BS1)

Prepared & Analyzed: 01/20/16

Calcium	455	10.0	mg/kg wet	500	91.0	82.9-118
Magnesium	475	5.00	"	500	94.9	77.1-123
Sodium	528	5.00	"	500	106	71-129

Duplicate (1601201-DUP1)

Source: 1601154-01

Prepared & Analyzed: 01/20/16

Calcium	1140	11.4	mg/kg dry	1190	3.88	200
Magnesium	459	5.69	"	439	4.31	200
Sodium	726	5.69	"	723	0.478	200

Matrix Spike (1601201-MS1)

Source: 1601154-01

Prepared & Analyzed: 01/20/16

Calcium	1650	11.4	mg/kg dry	527	1190	87.5	75-125
Magnesium	925	5.69	"	527	439	92.1	75-125
Sodium	1210	5.69	"	527	723	91.5	75-125

Matrix Spike Dup (1601201-MSD1)

Source: 1601154-01

Prepared & Analyzed: 01/20/16

Calcium	1670	11.4	mg/kg dry	527	1190	91.6	75-125	1.32	25
Magnesium	971	5.69	"	527	439	101	75-125	4.84	25
Sodium	1300	5.69	"	527	723	110	75-125	7.87	25

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Physical Parameters by APHA/ASTM/EPA Methods - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source	%REC		RPD		
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes

Batch 1601193 - General Preparation

LCS (1601193-BS1)					Prepared & Analyzed: 01/20/16						
pH	7.96	0.100	pH Units	8.00	99.5	95-105					
Duplicate (1601193-DUP1)					Source: 1601051-04 Prepared & Analyzed: 01/20/16						
pH	8.92	0.100	pH Units	9.11	2.11	20					

Batch 1601194 - General Preparation

Blank (1601194-BLK1)					Prepared & Analyzed: 01/20/16						
Specific Conductance (EC)	ND	0.0100	mmhos/cm								
LCS (1601194-BS1)					Prepared & Analyzed: 01/20/16						
Specific Conductance (EC)	0.504	0.0100	mmhos/cm	0.500	101	90-110					
Duplicate (1601194-DUP1)					Source: 1601051-04 Prepared & Analyzed: 01/20/16						
Specific Conductance (EC)	2.80	0.0100	mmhos/cm	2.24	22.1	20					QR-03

Batch 1601195 - General Preparation

Duplicate (1601195-DUP1)					Source: 1601144-01 Prepared: 01/20/16 Analyzed: 01/21/16						
% Solids	71.8		%	73.5	2.34	20					

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
1759 Redwing Lane
Broomfield CO, 80020

Project: Noble - Burke RG 24-8

Project Number: [none]
Project Manager: Paul Henehan

Reported:
01/21/16 15:08

Notes and Definitions

QR-03 The RPD value for the sample duplicate or MS/MSD was outside of QC acceptance limits due to matrix interference. QC batch accepted based on LCS and/or LCSD recovery and/or RPD values.

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.