

PICEANCE VLY NAD 83

RU 07-07S-093W

SR 43-12 Pad

SR 44-12 - Slot B5

Wellbore #1

Plan: Design #2 30Mar16 sam

Standard Planning Report

04 May, 2016

WPX

Planning Report

Database:	COMPASS	Local Co-ordinate Reference:	Well SR 44-12 (B5) - Slot B5
Company:	PICEANCE VLY NAD 83	TVD Reference:	KB @ 7381.00usft (HP 318)
Project:	RU 07-07S-093W	MD Reference:	KB @ 7381.00usft (HP 318)
Site:	SR 43-12 Pad	North Reference:	True
Well:	SR 44-12	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 30Mar16 sam		

Project	RU 07-07S-093W, Garfield County, CO		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Colorado Central Zone		Using geodetic scale factor

Site	SR 43-12 Pad			
Site Position:		Northing:	1,598,022.10 usft	Latitude: 39.452261
From: Map		Easting:	2,343,309.20 usft	Longitude: -107.825846
Position Uncertainty:	0.00 usft	Slot Radius:	0.000 in	Grid Convergence: -1.47 °

Well	SR 44-12 - Slot B5			
Well Position	+N/-S	-37.57 usft	Northing:	1,597,984.50 usft
	+E/-W	1.76 usft	Easting:	2,343,310.00 usft
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft
			Ground Level:	7,357.00 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	12/31/2009	10.43	65.79	52,412

Design	Design #2 30Mar16 sam			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (bearing)
	0.00	0.00	0.00	211.00

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
120.00	0.00	0.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	
286.67	5.00	240.00	286.46	-3.63	-6.29	3.00	3.00	0.00	240.00	
637.80	14.60	210.49	632.23	-49.55	-42.10	3.00	2.73	-8.40	-42.78	
4,871.46	14.60	210.49	4,729.18	-969.16	-583.53	0.00	0.00	0.00	0.00	
5,844.78	0.00	0.00	5,692.00	-1,075.44	-646.11	1.50	-1.50	0.00	180.00	10 acre SR 44-12 MV
9,534.78	0.00	0.00	9,382.00	-1,075.44	-646.11	0.00	0.00	0.00	0.00	

WPX
Planning Report

Database:	COMPASS	Local Co-ordinate Reference:	Well SR 44-12 (B5) - Slot B5
Company:	PICEANCE VLY NAD 83	TVD Reference:	KB @ 7381.00usft (HP 318)
Project:	RU 07-07S-093W	MD Reference:	KB @ 7381.00usft (HP 318)
Site:	SR 43-12 Pad	North Reference:	True
Well:	SR 44-12	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 30Mar16 sam		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
120.00	0.00	0.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 3.00									
286.67	5.00	240.00	286.46	-3.63	-6.29	6.36	3.00	3.00	0.00
Start turn DLS 3.00 TFO -42.78									
500.00	10.62	215.76	497.77	-24.26	-25.86	34.11	3.00	2.64	-11.36
637.80	14.60	210.49	632.23	-49.55	-42.10	64.15	3.00	2.88	-3.82
Hold 14.60 Inclination									
1,000.00	14.60	210.49	982.73	-128.22	-88.42	155.45	0.00	0.00	0.00
1,124.00	14.60	210.49	1,102.73	-155.16	-104.28	186.70	0.00	0.00	0.00
9 5/8"									
1,500.00	14.60	210.49	1,466.59	-236.83	-152.36	281.48	0.00	0.00	0.00
2,000.00	14.60	210.49	1,950.44	-345.44	-216.31	407.50	0.00	0.00	0.00
2,500.00	14.60	210.49	2,434.30	-454.04	-280.25	533.53	0.00	0.00	0.00
3,000.00	14.60	210.49	2,918.15	-562.65	-344.20	659.56	0.00	0.00	0.00
3,298.49	14.60	210.49	3,207.00	-627.49	-382.37	734.80	0.00	0.00	0.00
Top of "G" Sand									
3,448.33	14.60	210.49	3,352.00	-660.03	-401.53	772.56	0.00	0.00	0.00
Base of "G" Sand									
3,500.00	14.60	210.49	3,402.01	-671.26	-408.14	785.59	0.00	0.00	0.00
4,000.00	14.60	210.49	3,885.86	-779.86	-472.09	911.62	0.00	0.00	0.00
4,500.00	14.60	210.49	4,369.72	-888.47	-536.03	1,037.64	0.00	0.00	0.00
4,871.46	14.60	210.49	4,729.18	-969.16	-583.53	1,131.27	0.00	0.00	0.00
Start Drop -1.50									
5,000.00	12.67	210.49	4,854.09	-995.27	-598.91	1,161.57	1.50	-1.50	0.00
5,440.02	6.07	210.49	5,288.00	-1,056.98	-635.24	1,233.18	1.50	-1.50	0.00
Lower Wasatch									
5,500.00	5.17	210.49	5,347.69	-1,062.04	-638.22	1,239.06	1.50	-1.50	0.00
5,567.53	4.16	210.49	5,415.00	-1,066.77	-641.01	1,244.55	1.50	-1.50	0.00
Ohio Creek									
5,844.78	0.00	0.00	5,692.00	-1,075.44	-646.11	1,254.60	1.50	-1.50	0.00
Vertical - Mesaverde									
6,000.00	0.00	0.00	5,847.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
6,500.00	0.00	0.00	6,347.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
7,000.00	0.00	0.00	6,847.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
7,482.78	0.00	0.00	7,330.00	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
Approx Top Gas									
7,500.00	0.00	0.00	7,347.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
8,000.00	0.00	0.00	7,847.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
8,500.00	0.00	0.00	8,347.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
8,520.78	0.00	0.00	8,368.00	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
Cameo									
9,000.00	0.00	0.00	8,847.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
9,200.78	0.00	0.00	9,048.00	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
Coal D									
9,384.78	0.00	0.00	9,232.00	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
Rollins									
9,500.00	0.00	0.00	9,347.22	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
9,534.78	0.00	0.00	9,382.00	-1,075.44	-646.11	1,254.60	0.00	0.00	0.00
TD at 9534.78 - TD									

WPX

Planning Report

Database:	COMPASS	Local Co-ordinate Reference:	Well SR 44-12 (B5) - Slot B5
Company:	PICEANCE VLY NAD 83	TVD Reference:	KB @ 7381.00usft (HP 318)
Project:	RU 07-07S-093W	MD Reference:	KB @ 7381.00usft (HP 318)
Site:	SR 43-12 Pad	North Reference:	True
Well:	SR 44-12	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 30Mar16 sam		

Design Targets									
Target Name	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- hit/miss target	(°)	(bearing)	(usft)	(usft)	(usft)	(usft)	(usft)		
- Shape									
10 acre SR 44-12 MVR	0.00	0.00	5,692.00	-1,075.44	-646.11	1,596,926.00	2,342,636.60	39.449205	-107.828127
- plan hits target center									
- Circle (radius 50.00)									

Casing Points					
Measured Depth	Vertical Depth	Name		Casing Diameter	Hole Diameter
(usft)	(usft)			(in)	(in)
1,124.00	1,102.73	9 5/8"		9.625	13.500

Formations						
Measured Depth	Vertical Depth	Name	Lithology	Dip	Dip Direction	
(usft)	(usft)			(°)	(bearing)	
3,298.49	3,207.00	Top of "G" Sand		0.00		
3,448.33	3,352.00	Base of "G" Sand		0.00		
5,440.02	5,288.00	Lower Wasatch		0.00		
5,567.53	5,415.00	Ohio Creek		0.00		
5,844.78	5,692.00	Mesaverde		0.00		
7,482.78	7,330.00	Approx Top Gas		0.00		
8,520.78	8,368.00	Cameo		0.00		
9,200.78	9,048.00	Coal D		0.00		
9,384.78	9,232.00	Rollins		0.00		
9,534.78	9,382.00	TD		0.00		

Plan Annotations					
Measured Depth	Vertical Depth	Local Coordinates		Comment	
(usft)	(usft)	+N/-S	+E/-W		
(usft)	(usft)	(usft)	(usft)		
120.00	120.00	0.00	0.00	Start Build 3.00	
286.67	286.46	-3.63	-6.29	Start turn DLS 3.00 TFO -42.78	
637.80	632.23	-49.55	-42.10	Hold 14.60 Inclination	
4,871.46	4,729.18	-969.16	-583.53	Start Drop -1.50	
5,844.78	5,692.00	-1,075.44	-646.11	Vertical	
9,534.78	9,382.00	-1,075.44	-646.11	TD at 9534.78	