

Battlement Mesa 34F Pad Reclaim

Upper drainage about a 100' from the starting point will need to be dug out and re-sloped, replacing that section of liner.

Lower Drainage on the southeast side needs dug out and re-sloped, so water can continue down to the natural drainage. Will add some rock down the drain to help with erosion problems. Fix the upper French drain if we intern reclaim the site.

Drainage ditches need to be fixed prior to any other activities take place on the site. It's estimated to take 5 days to fix the drainages.

Intern reclaim, recon tour location back to its natural state leaving a portion of the pad around the existing wells. Spread the topsoil out across the site, add storm water measure and reseed disturb area. It's estimated it will take 4 weeks to move the dirt on the site and another 1 week to put seed and put storm water measures in place.

Start the working on the Drainage ditches August 15, 2016 with landowner and state permission and finish the drainage ditches repairs August 19, 2016.

Start location interim reclamation august 17, 2016 and finish the location reclamation roughly September 16, 2016.

Seed the location the Week of September 19th.

All the dates are contingent of weather conditions that could affect the reclaim of the site.

Battlement Mesa 34F Pad Reclamation Plan

Area to be
left for well
access

French Drain Repair Area

Area within Green
perimeter indicates
interim reclamation area

39.396693, -107.984691

Lower Drainage Repair Area

Upper Drainage Repair Area

