



- \*NOTE:**
- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
  - 2.) Topsoil Volume Based on 6" Soil Depth.
  - 3.) Total Disturbed Area = ±1.06 ac.

ESTIMATED EARTHWORK QUANTITIES (cy)				
ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	480	118	362	0
PIT	0			0
TOTALS	480	118	362	0

**Construction Plan Prepared for:**

Greenleaf Environmental Services

*Greenleaf Disposal 1 - Plat 2B*

**CONSTRUCTION LAYOUT**

136 East Third Street  
Rifle, Colorado 81650  
Ph. (970) 625-2720  
Fax (970) 625-2773

**BOOKCLIFF**  
Survey Services, Inc.

SCALE: 1" = 50'

DATE: 11/1/16

PLAT: 2B of 10

PROJECT: Greenleaf

DFT: WK

L:\2015\1028-01 GREEN LEAF\DWG\Green Leaf Drilling Permit.rvt.dwg