



APPROXIMATE EARTHWORK QUANTITIES	
(6") TOPSOIL STRIPPING	3,860 Cu. Yds.
REMAINING LOCATION	28,730 Cu. Yds.
TOTAL CUT	32,590 Cu. Yds.
FILL	28,730 Cu. Yds.
EXCESS MATERIAL	3,860 Cu. Yds.
TOPSOIL	3,860 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	0 Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±5.546
30' WIDE ACCESS ROAD R-O-W DISTURBANCE	±660'	±0.455
30' WIDE PIPELINE R-O-W DISTURBANCE	±1034'	±0.712
TOTAL SURFACE USE AREA		±6.713

REV: 03 01-09-17 S.S. (SHL CHANGES)

NOTES:

- Fill quantity includes 5% for compaction.
- Calculations based on 6" of topsoil stripping.

LARAMIE ENERGY, LLC

BRUTON 30-01 PAD
NE 1/4 NE 1/4, SECTION 30, T9S, R93W, 6th P.M.
MESA COUNTY, COLORADO

DRAWN BY: M.D.	DATE DRAWN: 05-29-15
SCALE: AS SHOWN	
CONSTRUCTION LAYOUT CROSS SECTIONS	FIGURE #2



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017