



FINISHED GRADE ELEVATION = 5346.5'

REV: 2 02-17-17 M.D. (ADD WELLS, COMPANY NAME, PAD & WELL CHANGES)

- NOTES:**
- Flare Stack is to be located a min. of 100' from the wellhead.
  - Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ.).
  - Underground utilities shown on this sheet are for visualization purposes only, actual locations to be determined prior to construction.

**FIFTH CREEK ENERGY COMPANY, LLC**

**RANDALL CREEK 29 SESE**  
**SE 1/4 SE 1/4, SECTION 29, T12N, R62W, 6th P.M.**  
**WELD COUNTY, COLORADO**

SURVEYED BY	GREG WEIMER, J.S.	02-10-17	SCALE
DRAWN BY	T.T.	01-13-15	1" = 80'
CONSTRUCTION LAYOUT		FIGURE #1	



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017