



APPROXIMATE EARTHWORK QUANTITIES	
(6") TOPSOIL STRIPPING	4,610 Cu. Yds.
REMAINING LOCATION	47,230 Cu. Yds.
TOTAL CUT	51,840 Cu. Yds.
FILL	47,230 Cu. Yds.
EXCESS MATERIAL	4,610 Cu. Yds.
TOPSOIL	4,610 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	0 Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.001
30' WIDE ACCESS ROAD R-O-W DISTURBANCE	±1363'	±0.917
TOTAL SURFACE USE AREA		±6.918

REV: 2 04-27-17 S.S. (SHL MOVE)

- NOTES:**
- Fill quantity includes 5% for compaction.
 - Calculations based on 6" of topsoil stripping.
 - Topsoil should not be stripped below finished grade on substructure area.

LARAMIE ENERGY, LLC

BRUTON 30-03 PAD
NE 1/4 NW 1/4, SECTION 30, T9S, R93W, 6th P.M.
MESA COUNTY, COLORADO



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

DRAWN BY: M.D.	DATE DRAWN: 04-29-15
SCALE: AS SHOWN	
CONSTRUCTION LAYOUT CROSS SECTIONS	FIGURE #2