



#### Plan of Development

**Access:** Existing Access with some road maintenance/upgrades.

**Completions:** The TR 1-23-597 Pad will be utilized as a remote frac pad for the TR 32-23-597 pad. 2-10" surface poly water supply lines will be installed from the proposed above ground valve set for the 10" water lines north west of the TR 1-23-597 pad to the TR 1-23-597 pad. 3-4.5" temporary surface frac lines will be installed from the TR 1-23-597 Frac Pad to the TR 32-23-597 pad following existing Right-of-Ways. Water will be delivered to the TR 1-23-597 using the proposed 10" water pipelines and other existing waterline infrastructure.

**Flowback:** TR 1-23-597 Frac Pad.

**Production:** The existing production equipment will be removed during completions operations and will be re-installed once the completions crew move off location.

#### Legend

- Existing Pad Edge
- Existing Road
- Existing Production Equipment
- Existing Limit of Disturbance
- Existing Fence
- Proposed Temporary Frac Lines (3-4.5" Steel)
- Proposed Frac Water Supply Line (2-10" Poly)
- Proposed Water Line (2-10")
- Existing Gas Pipeline
- Existing Water Pipeline
- Existing Road
- Existing Pad

**TEP Rocky Mountain LLC**

**TR 1-23-597 Frac Pad POD  
T5S R97W, Section 23**

**March 22, 2017**

