



FINISHED GRADE ELEVATION = 4774.1'

APPROXIMATE EARTHWORK QUANTITIES	
TOTAL CUT	6,200 Cu. Yds.
FILL	6,200 Cu. Yds.
EXCESS MATERIAL	0 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	0 Cu. Yds.

REV: 7 09-26-17 D.COX (SL MOVE & PAD EXPANSION)

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
PROPOSED EXPANSION DISTURBANCE	NA	±2.087
EXISTING DISTURBANCE	NA	±2.353
TOTAL SURFACE USE AREA		±4.440

WELL TABULATION	
X44-22-21XRLNB	1120' FSL 505' FEL

- NOTES:**
- Contours shown at 2' intervals.
 - Round corners at 35' radius or as needed.
 - Cut slopes 3:1 (Typ.).
 - Fill slopes 4:1 (Typ.).
 - Underground utilities shown on this sheet are for visualization purposes only, actual locations to be determined prior to construction.



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

**BONANZA CREEK ENERGY
OPERATING COMPANY, LLC**

**MUSTANG 44-22 PAD
SE 1/4 SE 1/4, SECTION 22, T4N, R63W, 6th P.M.
WELD COUNTY, COLORADO**

SURVEYED BY	CHAD MEIERS	08-22-17	SCALE
DRAWN BY	K.B.	09-21-16	1" = 60'

INITIAL PLAT