



REV: 3 08-23-17 K.B. (NAME CHANGE)

NOTE: Earthwork calculations require a fill @ some location stakes for balance. All fill is to be compacted to a minimum of 95% of the maximum dry density obtained by AASHTO method t-99.

FINISHED GRADE ELEVATION = 4972.1'

- NOTES:**
- Round corners at 35' radius or as needed.
  - Construct diversion ditches as needed.
  - Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ.).

**GREAT WESTERN OPERATING COMPANY**

**BRANT LD PAD**  
SE 1/4 NE 1/4, SECTION 11, T1S, R67W, 6th P.M.  
ADAMS COUNTY, COLORADO

SURVEYED BY	CHAD MEIERS, D.N.	08-10-17	SCALE
DRAWN BY	K.B.	06-30-17	1" = 100'

**CONSTRUCTION LAYOUT** **FIGURE #1**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017