



APPROXIMATE EARTHWORK QUANTITIES	
TOTAL CUT	5,980 Cu. Yds.
FILL	5,920 Cu. Yds.
EXCESS MATERIAL	60 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	60 Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE AREA OF MAX. DISTURBANCE	NA	±4.618
ROAD DISTURBANCE	±45'	±0.031
TOTAL SURFACE USE AREA		±4.649

WELL TABULATION	
V41-27-28XRLNB	1764' FNL 211' FWL

FINISHED GRADE ELEVATION = 4749.7'

REV: 3 09-26-17 D.COX (PAD MOVE)

- NOTES:
- Contours shown at 2' intervals.
 - Cut slopes 3:1 (Typ.).
 - Fill slopes 4:1 (Typ.).

BONANZA CREEK ENERGY
OPERATING COMPANY, LLC

MUSTANG 12-26 PAD
SW 1/4 NW 1/4, SECTION 26, T4N, R63W, 6th P.M.
WELD COUNTY, COLORADO

SURVEYED BY	CHAD MEIERS, T.M.	09-01-17	SCALE
DRAWN BY	M.D.	05-05-17	1" = 60'

INITIAL PLAT



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017