

NOTE:
Well positions & pad corners are calculated & not set on ground. Position to be staked & field verified at a later date.

FINISHED GRADE ELEVATION = 8109.3'

REV: 5 12-07-17 M.D. (PAD & SHL CHANGE)


- NOTES:**
- Flare Stack is to be located a min. of 100' from the wellhead.
 - Round corners at 35' radius or as needed.
 - Contours shown at 2' intervals.
 - Cut/Fill slopes 1 1/2:1 (Typ.).
 - Production Facility to be Removed and Relocated.

Gunnison Energy LLC


TRAIL GULCH UNIT 1090 30-H1 PAD
SW 1/4 SE 1/4, SECTION 30, T10S, R90W, 6th P.M.
GUNNISON COUNTY, COLORADO

UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

SURVEYED BY	MARTIN PIERCE	11-03-16	SCALE
DRAWN BY	C.D.L.	03-29-17	1" = 60'
CONSTRUCTION LAYOUT		FIGURE #1	



- SWMP LEGEND:**
- CB - CATCH BASIN
 - CD - CHECK DAM (GRAVEL)
 - ECB - EROSION CONTROL BLANKET
 - LS - LEVEL SPREADER
 - M - CERTIFIED STRAW MULCH
 - SCE - STABILIZED CONSTRUCTION ENTRANCE



NOTE:
Well positions & pad corners are calculated & not set on ground. Position to be staked & field verified at a later date.

FINISHED GRADE ELEVATION = 8109.3'

REV: 3 12-07-17 M.D. (PAD & SHL CHANGE)

- NOTES:**
- Flare Stack is to be located a min. of 100' from the wellhead.
 - Round corners at 35' radius or as needed.
 - Contours shown at 2' intervals.
 - Cut/Fill slopes 1 1/2:1 (Typ.).
 - Production Facility to be Removed and Relocated.

Gunnison Energy LLC

TRAIL GULCH UNIT 1090 30-H1 PAD
SW 1/4 SE 1/4, SECTION 30, T10S, R90W, 6th P.M.
GUNNISON COUNTY, COLORADO




UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017


SURVEYED BY	MARTIN PIERCE	11-03-16	SCALE
DRAWN BY	C.D.L.	03-29-17	1" = 60'

CONSTRUCTION LAYOUT FIGURE #2

1" = 40'
 X-Section
 Scale
 1" = 100'




"E" - "E"




"D" - "D"


NOTE:
 Well positions & pad corners
 are calculated & not set on
 ground. Position to be staked
 & field verified at a later date.



"C" - "C"



"B" - "B"



"A" - "A"

APPROXIMATE EARTHWORK QUANTITIES	
(6") TOPSOIL STRIPPING	4,360 Cu. Yds.
REMAINING LOCATION	51,700 Cu. Yds.
TOTAL CUT	56,060 Cu. Yds.
FILL	51,700 Cu. Yds.
EXCESS MATERIAL	4,360 Cu. Yds.
TOPSOIL	4,360 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	0 Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±5.655
30' WIDE ROAD RE-ROUTE R-O-W DISTURBANCE	±883'	±0.608
30' WIDE PIPELINE R-O-W DISTURBANCE	±414'	±0.285
TOTAL SURFACE USE AREA		±6.548

REV: 5 12-07-17 M.D. (PAD & SHL CHANGE)

- NOTES:**
- Fill quantity includes 5% for compaction.
 - Calculations based on 6" of topsoil stripping.
 - Cut/Fill slopes 1 1/2:1 (Typ.).



Gunnison Energy LLC

TRAIL GULCH UNIT 1090 30-H1 PAD
 SW 1/4 SE 1/4, SECTION 30, T10S, R90W, 6th P.M.
 GUNNISON COUNTY, COLORADO



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

SURVEYED BY	MARTIN PIERCE	11-03-16	SCALE
DRAWN BY	C.D.L.	03-29-17	AS SHOWN
CONSTRUCTION LAYOUT CROSS SECTIONS			FIGURE #3



SURFACE USE DISTURBANCE SUMMARY (SUDS)			
	Length (ft)	Width (ft)	Approx. Acres of Disturbance
Well Pad (including cuts/fills)	N/A	N/A	±5.340
Topsoil Piles	N/A	N/A	±0.315
Proposed Road Re-Route	±883'	30'	±0.608
Proposed Pipeline	±414'	30'	±0.285
Total Acres of Disturbance			±6.548

REV: 4 12-07-17 M.D. (PAD & SHL CHANGE)


Gunnison Energy LLC

TRAIL GULCH UNIT 1090 30-H1 PAD
 SW 1/4 SE 1/4, SECTION 30, T10S, R90W, 6th P.M.
 GUNNISON COUNTY, COLORADO

SURVEYED BY	MARTIN PIERCE	11-03-16	SCALE
DRAWN BY	C.D.L.	03-29-17	1" = 60'
ACREAGES		EXHIBIT 1	



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017



Harold Marshall

NOTE:
Well positions & pad corners are calculated & not set on ground. Position to be staked & field verified at a later date.



APPROXIMATE UN-RECLAIMED ACREAGE = ±1.428 ACRES
 APPROXIMATE RECLAIMED ACREAGE = ±4.227 ACRES
 TOTAL ACREAGE = ±5.655 ACRES

NOTES:
 • Contours shown at 2' intervals.

REV: 3 12-05-17 C.D.L. (PAD CHANGE)

Gunnison Energy LLC

TRAIL GULCH UNIT 1090 30-H1 PAD
 SW 1/4 SE 1/4, SECTION 30, T10S, R90W, 6th P.M.
 GUNNISON COUNTY, COLORADO

SURVEYED BY	MARTIN PIERCE	11-03-16	SCALE
DRAWN BY	C.D.L.	03-29-17	1" = 60'
INTERIM RECLAMATION PLAN			FIGURE #5



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017