



REV: 1 01-25-18 C.IVIE (WELL & PAD NAME CHANGE)

FINISHED GRADE ELEVATION = 5012.7'

NOTES:

- Contours shown at 2' intervals.
- Cut/Fill slopes 1 1/2:1 (Typ.)

NOTE: Earthwork calculations require a fill @ some of the location stakes for balance. All fill is to be compacted to a minimum of 95% of the maximum dry density obtained by AASHTO method t-99.

VERDAD RESOURCES LLC

HDI KF 01 65 10 PAD
SE 1/4 SE 1/4, SECTION 10, T1N, R65W, 6th P.M.
WELD COUNTY, COLORADO

SURVEYED BY	GREG WEIMER	10-30-17	SCALE
DRAWN BY	D.J.W.	11-27-17	1" = 100'
CONSTRUCTION LAYOUT		FIGURE #1	



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017