

FINISHED GRADE ELEVATION = 5813.0' REV: 2 06-06-18 M.D. (PAD NAME CHANGE)

NOTE: Earthwork calculations require a fill @ the location stakes for balance. All fill is to be compacted to a minimum of 95% of the maximum dry density obtained by AASHTO method t-99.

- NOTES:**
- Round corners at 35' radius or as needed.
  - Construct diversion ditches as needed.
  - Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ.).

**TEP Rocky Mountain LLC**


**RMV 143-18 FRAC PAD**  
 NW 1/4 SE 1/4, SECTION 18, T6S, R94W, 6th P.M.  
 GARFIELD COUNTY, COLORADO



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

|                            |                 |                |              |
|----------------------------|-----------------|----------------|--------------|
| <b>SURVEYED BY</b>         | CODY RICH, D.R. | 03-09-18       | <b>SCALE</b> |
| <b>DRAWN BY</b>            | T.L.L.          | 03-13-18       | 1" = 60'     |
| <b>CONSTRUCTION LAYOUT</b> |                 | <b>PLAT #1</b> |              |

X-Section Scale  
1" = 40'  
1" = 100'



| APPROXIMATE EARTHWORK QUANTITIES                          |                       |
|---|-----------------------|
| (6") TOPSOIL STRIPPING (NEW CONSTRUCTION ONLY)            | 920 Cu. Yds.          |
| REMAINING LOCATION  | 2,120 Cu. Yds.        |
| <b>TOTAL CUT</b>  | <b>3,040 Cu. Yds.</b> |
| <b>FILL</b>   | <b>2,120 Cu. Yds.</b> |
| EXCESS MATERIAL   | 920 Cu. Yds.          |
| TOPSOIL   | 920 Cu. Yds.          |
| <b>EXCESS UNBALANCE</b><br>(After Interim Rehabilitation) | <b>0 Cu. Yds.</b>     |

| APPROXIMATE SURFACE DISTURBANCE AREAS |          |               |
|---------------------------------------|----------|---------------|
|                                       | DISTANCE | ACRES         |
| WELL SITE DISTURBANCE                 | NA       | ±2.132        |
| <b>TOTAL SURFACE USE AREA</b>         |          | <b>±2.132</b> |

REV: 2 06-06-18 M.D. (PAD NAME CHANGE)

**NOTES:**

- Volumes shown are for new construction only.
- Fill quantity includes 5% for compaction.
- Calculations based on 6" of topsoil stripping.
- Cut/Fill slopes 1 1/2:1 (Typ.).

**TEP Rocky Mountain LLC**

**RMV 143-18 FRAC PAD**  
NW 1/4 SE 1/4, SECTION 18, T6S, R94W, 6th P.M.  
GARFIELD COUNTY, COLORADO



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

|   |                 |          |                |
|---|-----------------|----------|----------------|
| SURVEYED BY                               | CODY RICH, D.R. | 03-09-18 | SCALE          |
| DRAWN BY                                  | T.L.L.          | 03-13-18 | AS SHOWN       |
| <b>CONSTRUCTION LAYOUT CROSS SECTIONS</b> |                 |          | <b>PLAT #2</b> |