



FINISHED SUB-GRADE ELEVATION = 5201.1'

- NOTES:**
- Flare stack is to be located a min. of 100' from the wellhead.
 - Round corners at 35' radius or as needed.
 - Construct diversion ditches as needed.
 - Contours shown at 2' intervals.
 - Cut/Fill slopes 2:1 (Typ. except where noted).



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

ENERPLUS RESOURCES (USA) CORPORATION

ALBERTA CITIES PAD EAST
SE 1/4 SE 1/4, SECTION 20, T8N, R67W, 6th P.M.
WELD COUNTY, COLORADO

SURVEYED BY	G. WEIMER, J.F.	09-18-17	SCALE
DRAWN BY	E.C.	10-03-17	1" = 80'
CONSTRUCTION LAYOUT		FIGURE #1	