

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



OGCC RECEPTION

Receive Date:

08/06/2019

Document Number:

402135186**Produced Water Transfer System**

The Flowline Report, Form 44, shall be submitted to register, report realignment, report removal from service, or report abandonment of Off-Location Flowlines, Produced Water Transfer Systems, Domestic Taps, or Crude Oil Transfer Lines as required by the 1100 Series Rules. The Form shall also be submitted to report Grade 1 Gas Leaks from Flowlines per Rule 1104.k.

**Operator Information**

OGCC Operator Number: 10686 Contact Person: Anita Cuevas  
Company Name: NOBLE MIDSTREAM SERVICES LLC Phone: (303) 6537960  
Address: 1625 BROADWAY #2200 Email: anita.cuevas@nblmidstream.com  
City: DENVER State: CO Zip: 80202  
Is the Operator a Tier One member of the Utility Notification Center of Colorado (UNCC) that participates in Colorado's One Call notification system? Yes ☒ No ☐

**PRODUCED WATER TRANSFER SYSTEM****PRODUCED WATER TRANSFER SYSTEM IDENTIFICATION**

Facility ID: 462751 Transfer System Name: MUP-06-TLN-200-L3 Action Type: As Built  
Estimated Daily Transfer Volume : 12500 Facility Surety ID: 20180081  
(barrels) Financial Assurance Rule 711

**PRODUCED WATER TRANSFER SYSTEM REGISTRATION**Planned Construction Date: 02/25/2019

A representative legal location and associated latitude and longitude near the center of the transfer system.

County: WELD  
Qtr Qtr: SWSW Section: 22 Township: 3N Range: 64W Meridian: 6  
Latitude: 40.204911 Longitude: -104.546388

**PRODUCED WATER TRANSFER LINE AS-BUILT SPECIFICATIONS**Date Produced Water Transfer Line was Placed into Service: 07/12/2019**Pipe Description and Testing**

Type of Fluid Transferred: Produced Water Pipe Material: Other Standard Dimension Ratio: (for HDPE pipe only)  
Max outer Diameter (inches): 6.930 Wall Thickness: 0.665 Weight (lb/ft): 9.20 Grade:   
Coating: False Pipe Material: Native Materials Burial Depth: 4  
Max Anticipated Operating PSI: 740 Testing Pressure: 1081 Test Date: 06/22/2019

**Description of Corrosion Protection:**N/A - FlexSteel**Description of Integrity Management Program:**A post construction hydrostatic test has been performed and is attached. Continuous pressure monitoring has been implemented as the integrity method.

Construction method used for all public by-ways, road crossings, sensitive wildlife habitats, sensitive areas and natural and manmade watercourses (i.e., bored and cased or bored only)

No crossings.

#### OPERATOR COMMENTS AND SUBMITTAL

Comments Pipe Grade is 750 psi

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.  
Signed: \_\_\_\_\_ Date: 08/06/2019 Email: anita.cuevas@nblmidstream.com

Print Name: Anita Cuevas Title: Regulatory Contractor

Based on the information provided herein, this Flowline Report complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

#### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
402135186	Form44 Submitted
402135384	PRODUCED WATER TRANSFER SYSTEM GEODATABASE GDB
402135385	AFFIDAVIT OF COMPLETION
402135387	PRESSURE TEST
402135403	LAYOUT DRAWING-ACTUAL

Total Attach: 5 Files