

ConocoPhillips RBU Gold Data

Niobrara Central Zone

Rush

Rush 4-65 29-30 3DH

Rush 4-65 29-30 3DH

Plan: Design A

Standard Planning Report

30 August, 2018

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Project	Niobrara Central Zone, Colorado Central Zone, FIPS Zone: 0502		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Colorado Central Zone		Using geodetic scale factor

Site	Rush				
Site Position:		Northing:	1,674,265.179 usft	Latitude:	39° 40' 55.358 N
From:	Lat/Long	Easting:	3,220,614.549 usft	Longitude:	104° 42' 58.151 W
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "	Grid Convergence:	0.49 °

Well	Rush 4-65 29-30 3DH					
Well Position	+N/-S	-3,996.31 ft	Northing:	1,670,363.884 usft	Latitude:	39° 40' 15.840 N
	+E/-W	10,988.83 ft	Easting:	3,231,637.290 usft	Longitude:	104° 40' 37.620 W
Position Uncertainty		2.00 ft	Wellhead Elevation:	5,695.50 ft	Ground Level:	5,695.50 ft

Wellbore	Rush 4-65 29-30 3DH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2018	12/1/2018	8.14	66.27	51,839.78210647

Design	Design A			
Audit Notes:				
Version:	0	Phase:	PLAN	Tie On Depth: 0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	271.31

Plan Survey Tool Program	Date	8/29/2018			
Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.00	2,216.00	Design A (Rush 4-65 29-30 3DH)	Gyro-BM-MS	
				Gyro - bat/mem drop m/s	
2	2,216.00	5,538.00	Design A (Rush 4-65 29-30 3DH)	MWD+IFR_No SAG	
				MWD + IFR (No SAG) corre	
3	5,538.00	6,384.84	Design A (Rush 4-65 29-30 3DH)	MWD+IFR_No SAG	
				MWD + IFR (No SAG) corre	
4	6,384.84	7,587.97	Design A (Rush 4-65 29-30 3DH)	MWD+IFR_No SAG	
				MWD + IFR (No SAG) corre	
5	7,587.97	8,370.52	Design A (Rush 4-65 29-30 3DH)	MWD+IFR_No SAG	
				MWD + IFR (No SAG) corre	
6	8,370.52	18,157.61	Design A (Rush 4-65 29-30 3DH)	MWD+IFR_No SAG	
				MWD + IFR (No SAG) corre	

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,538.00	0.00	0.00	5,538.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,384.84	12.70	296.09	6,377.92	41.11	-83.96	1.50	1.50	0.00	296.09	
7,587.97	12.70	296.09	7,551.61	157.45	-321.57	0.00	0.00	0.00	0.00	
8,370.52	89.67	270.23	8,009.00	204.41	-879.69	10.00	9.83	-3.30	-26.45	Rush 4-65 29-30 3D
18,157.61	89.67	270.23	8,066.00	244.06	-10,666.53	0.00	0.00	0.00	0.00	Rush 4-65 29-30 3D

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
SHL: 1331' FSL, 422' FWL									
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,747.00	0.00	0.00	1,747.00	0.00	0.00	0.00	0.00	0.00	0.00
Fox Hills Top									
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,016.00	0.00	0.00	2,016.00	0.00	0.00	0.00	0.00	0.00	0.00
Pierre Top - Fox Hills Base - 9-5/8" Casing									
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,216.00	0.00	0.00	2,216.00	0.00	0.00	0.00	0.00	0.00	0.00
Surface Casing									
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	0.00	0.00
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	0.00	0.00
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00
5,538.00	0.00	0.00	5,538.00	0.00	0.00	0.00	0.00	0.00	0.00
5,600.00	0.93	296.09	5,600.00	0.22	-0.45	0.46	1.50	1.50	0.00
5,700.00	2.43	296.09	5,699.95	1.51	-3.08	3.12	1.50	1.50	0.00
5,800.00	3.93	296.09	5,799.79	3.95	-8.07	8.16	1.50	1.50	0.00
5,900.00	5.43	296.09	5,899.46	7.54	-15.39	15.56	1.50	1.50	0.00
6,000.00	6.93	296.09	5,998.87	12.27	-25.06	25.34	1.50	1.50	0.00
6,100.00	8.43	296.09	6,097.97	18.15	-37.06	37.47	1.50	1.50	0.00
6,200.00	9.93	296.09	6,196.69	25.16	-51.39	51.95	1.50	1.50	0.00
6,300.00	11.43	296.09	6,294.96	33.31	-68.04	68.78	1.50	1.50	0.00
6,384.84	12.70	296.09	6,377.92	41.11	-83.96	84.88	1.50	1.50	0.00
EOB: 1372' FSL, 338' FWL									
6,400.00	12.70	296.09	6,392.71	42.58	-86.96	87.91	0.00	0.00	0.00
6,500.00	12.70	296.09	6,490.26	52.25	-106.71	107.87	0.00	0.00	0.00
6,600.00	12.70	296.09	6,587.81	61.92	-126.46	127.84	0.00	0.00	0.00
6,700.00	12.70	296.09	6,685.37	71.59	-146.20	147.80	0.00	0.00	0.00
6,800.00	12.70	296.09	6,782.92	81.26	-165.95	167.77	0.00	0.00	0.00
6,900.00	12.70	296.09	6,880.47	90.93	-185.70	187.73	0.00	0.00	0.00
7,000.00	12.70	296.09	6,978.02	100.60	-205.45	207.70	0.00	0.00	0.00
7,100.00	12.70	296.09	7,075.58	110.27	-225.20	227.66	0.00	0.00	0.00
7,200.00	12.70	296.09	7,173.13	119.94	-244.95	247.63	0.00	0.00	0.00
7,300.00	12.70	296.09	7,270.68	129.61	-264.70	267.59	0.00	0.00	0.00
7,400.00	12.70	296.09	7,368.23	139.28	-284.45	287.56	0.00	0.00	0.00
7,500.00	12.70	296.09	7,465.79	148.95	-304.19	307.52	0.00	0.00	0.00
7,587.97	12.70	296.09	7,551.60	157.45	-321.57	325.09	0.00	0.00	0.00
KOP: 1488' FSL, 100' FWL									
7,600.00	13.79	293.84	7,563.31	158.62	-324.07	327.61	10.00	9.04	-18.69
7,650.00	18.46	287.35	7,611.34	163.39	-337.08	340.73	10.00	9.34	-12.99
7,700.00	23.26	283.43	7,658.05	168.04	-354.25	358.01	10.00	9.61	-7.83
7,750.00	28.13	280.81	7,703.09	172.55	-375.45	379.30	10.00	9.74	-5.25
7,800.00	33.04	278.90	7,746.12	176.87	-400.51	404.45	10.00	9.81	-3.81
7,850.00	37.97	277.44	7,786.81	180.98	-429.25	433.28	10.00	9.86	-2.92
7,878.71	40.81	276.75	7,809.00	183.23	-447.33	451.40	10.00	9.88	-2.44
Niobrara Top									
7,900.00	42.91	276.28	7,824.85	184.83	-461.44	465.55	10.00	9.89	-2.20
7,950.00	47.86	275.31	7,859.96	188.41	-496.84	501.02	10.00	9.90	-1.94
8,000.00	52.82	274.48	7,891.86	191.69	-535.18	539.43	10.00	9.92	-1.66
8,050.00	57.79	273.75	7,920.31	194.63	-576.17	580.47	10.00	9.93	-1.45
8,100.00	62.75	273.10	7,945.10	197.22	-619.50	623.85	10.00	9.94	-1.30
8,150.00	67.73	272.51	7,966.03	199.44	-664.84	669.22	10.00	9.94	-1.19
8,200.00	72.70	271.96	7,982.95	201.27	-711.83	716.25	10.00	9.95	-1.11
8,250.00	77.67	271.43	7,995.73	202.69	-760.13	764.57	10.00	9.95	-1.05
8,266.36	79.30	271.26	7,999.00	203.07	-776.16	780.60	10.00	9.95	-1.02
D Chalk Top									
8,300.00	82.65	270.93	8,004.28	203.70	-809.37	813.82	10.00	9.95	-1.00

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
8,350.00	87.62	270.43	8,008.51	204.29	-859.17	863.62	10.00	9.95	-0.99	
8,370.52	89.67	270.23	8,009.00	204.41	-879.69	884.13	10.00	9.95	-0.98	
BPI/LP: 1532' FSL, 460' FEL										
8,400.00	89.67	270.23	8,009.17	204.53	-909.17	913.61	0.00	0.00	0.00	
8,500.00	89.67	270.23	8,009.75	204.94	-1,009.16	1,013.59	0.00	0.00	0.00	
8,600.00	89.67	270.23	8,010.34	205.34	-1,109.16	1,113.57	0.00	0.00	0.00	
8,700.00	89.67	270.23	8,010.92	205.75	-1,209.16	1,213.55	0.00	0.00	0.00	
8,800.00	89.67	270.23	8,011.50	206.15	-1,309.16	1,313.53	0.00	0.00	0.00	
8,900.00	89.67	270.23	8,012.08	206.56	-1,409.15	1,413.51	0.00	0.00	0.00	
9,000.00	89.67	270.23	8,012.67	206.96	-1,509.15	1,513.49	0.00	0.00	0.00	
9,100.00	89.67	270.23	8,013.25	207.37	-1,609.15	1,613.47	0.00	0.00	0.00	
9,200.00	89.67	270.23	8,013.83	207.77	-1,709.15	1,713.45	0.00	0.00	0.00	
9,300.00	89.67	270.23	8,014.41	208.18	-1,809.14	1,813.43	0.00	0.00	0.00	
9,400.00	89.67	270.23	8,015.00	208.58	-1,909.14	1,913.41	0.00	0.00	0.00	
9,500.00	89.67	270.23	8,015.58	208.99	-2,009.14	2,013.39	0.00	0.00	0.00	
9,600.00	89.67	270.23	8,016.16	209.39	-2,109.14	2,113.37	0.00	0.00	0.00	
9,700.00	89.67	270.23	8,016.74	209.80	-2,209.13	2,213.35	0.00	0.00	0.00	
9,800.00	89.67	270.23	8,017.33	210.20	-2,309.13	2,313.33	0.00	0.00	0.00	
9,900.00	89.67	270.23	8,017.91	210.61	-2,409.13	2,413.32	0.00	0.00	0.00	
10,000.00	89.67	270.23	8,018.49	211.01	-2,509.13	2,513.30	0.00	0.00	0.00	
10,100.00	89.67	270.23	8,019.07	211.42	-2,609.12	2,613.28	0.00	0.00	0.00	
10,200.00	89.67	270.23	8,019.66	211.82	-2,709.12	2,713.26	0.00	0.00	0.00	
10,300.00	89.67	270.23	8,020.24	212.23	-2,809.12	2,813.24	0.00	0.00	0.00	
10,400.00	89.67	270.23	8,020.82	212.63	-2,909.12	2,913.22	0.00	0.00	0.00	
10,500.00	89.67	270.23	8,021.40	213.04	-3,009.11	3,013.20	0.00	0.00	0.00	
10,600.00	89.67	270.23	8,021.98	213.44	-3,109.11	3,113.18	0.00	0.00	0.00	
10,700.00	89.67	270.23	8,022.57	213.85	-3,209.11	3,213.16	0.00	0.00	0.00	
10,800.00	89.67	270.23	8,023.15	214.26	-3,309.11	3,313.14	0.00	0.00	0.00	
10,900.00	89.67	270.23	8,023.73	214.66	-3,409.10	3,413.12	0.00	0.00	0.00	
11,000.00	89.67	270.23	8,024.31	215.07	-3,509.10	3,513.10	0.00	0.00	0.00	
11,100.00	89.67	270.23	8,024.90	215.47	-3,609.10	3,613.08	0.00	0.00	0.00	
11,200.00	89.67	270.23	8,025.48	215.88	-3,709.10	3,713.06	0.00	0.00	0.00	
11,300.00	89.67	270.23	8,026.06	216.28	-3,809.09	3,813.04	0.00	0.00	0.00	
11,400.00	89.67	270.23	8,026.64	216.69	-3,909.09	3,913.02	0.00	0.00	0.00	
11,500.00	89.67	270.23	8,027.23	217.09	-4,009.09	4,013.00	0.00	0.00	0.00	
11,600.00	89.67	270.23	8,027.81	217.50	-4,109.09	4,112.99	0.00	0.00	0.00	
11,700.00	89.67	270.23	8,028.39	217.90	-4,209.08	4,212.97	0.00	0.00	0.00	
11,800.00	89.67	270.23	8,028.97	218.31	-4,309.08	4,312.95	0.00	0.00	0.00	
11,900.00	89.67	270.23	8,029.56	218.71	-4,409.08	4,412.93	0.00	0.00	0.00	
12,000.00	89.67	270.23	8,030.14	219.12	-4,509.08	4,512.91	0.00	0.00	0.00	
12,100.00	89.67	270.23	8,030.72	219.52	-4,609.07	4,612.89	0.00	0.00	0.00	
12,200.00	89.67	270.23	8,031.30	219.93	-4,709.07	4,712.87	0.00	0.00	0.00	
12,300.00	89.67	270.23	8,031.89	220.33	-4,809.07	4,812.85	0.00	0.00	0.00	
12,400.00	89.67	270.23	8,032.47	220.74	-4,909.07	4,912.83	0.00	0.00	0.00	
12,500.00	89.67	270.23	8,033.05	221.14	-5,009.06	5,012.81	0.00	0.00	0.00	
12,600.00	89.67	270.23	8,033.63	221.55	-5,109.06	5,112.79	0.00	0.00	0.00	
12,700.00	89.67	270.23	8,034.22	221.95	-5,209.06	5,212.77	0.00	0.00	0.00	
12,800.00	89.67	270.23	8,034.80	222.36	-5,309.06	5,312.75	0.00	0.00	0.00	
12,900.00	89.67	270.23	8,035.38	222.76	-5,409.05	5,412.73	0.00	0.00	0.00	
13,000.00	89.67	270.23	8,035.96	223.17	-5,509.05	5,512.71	0.00	0.00	0.00	
13,100.00	89.67	270.23	8,036.54	223.57	-5,609.05	5,612.69	0.00	0.00	0.00	
13,200.00	89.67	270.23	8,037.13	223.98	-5,709.05	5,712.67	0.00	0.00	0.00	
13,300.00	89.67	270.23	8,037.71	224.38	-5,809.04	5,812.66	0.00	0.00	0.00	

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
13,400.00	89.67	270.23	8,038.29	224.79	-5,909.04	5,912.64	0.00	0.00	0.00
13,500.00	89.67	270.23	8,038.87	225.19	-6,009.04	6,012.62	0.00	0.00	0.00
13,600.00	89.67	270.23	8,039.46	225.60	-6,109.04	6,112.60	0.00	0.00	0.00
13,700.00	89.67	270.23	8,040.04	226.00	-6,209.03	6,212.58	0.00	0.00	0.00
13,800.00	89.67	270.23	8,040.62	226.41	-6,309.03	6,312.56	0.00	0.00	0.00
13,900.00	89.67	270.23	8,041.20	226.81	-6,409.03	6,412.54	0.00	0.00	0.00
14,000.00	89.67	270.23	8,041.79	227.22	-6,509.03	6,512.52	0.00	0.00	0.00
14,100.00	89.67	270.23	8,042.37	227.62	-6,609.02	6,612.50	0.00	0.00	0.00
14,200.00	89.67	270.23	8,042.95	228.03	-6,709.02	6,712.48	0.00	0.00	0.00
14,300.00	89.67	270.23	8,043.53	228.43	-6,809.02	6,812.46	0.00	0.00	0.00
14,400.00	89.67	270.23	8,044.12	228.84	-6,909.01	6,912.44	0.00	0.00	0.00
14,500.00	89.67	270.23	8,044.70	229.24	-7,009.01	7,012.42	0.00	0.00	0.00
14,600.00	89.67	270.23	8,045.28	229.65	-7,109.01	7,112.40	0.00	0.00	0.00
14,700.00	89.67	270.23	8,045.86	230.05	-7,209.01	7,212.38	0.00	0.00	0.00
14,800.00	89.67	270.23	8,046.45	230.46	-7,309.00	7,312.36	0.00	0.00	0.00
14,900.00	89.67	270.23	8,047.03	230.86	-7,409.00	7,412.34	0.00	0.00	0.00
15,000.00	89.67	270.23	8,047.61	231.27	-7,509.00	7,512.33	0.00	0.00	0.00
15,100.00	89.67	270.23	8,048.19	231.67	-7,609.00	7,612.31	0.00	0.00	0.00
15,200.00	89.67	270.23	8,048.78	232.08	-7,708.99	7,712.29	0.00	0.00	0.00
15,300.00	89.67	270.23	8,049.36	232.48	-7,808.99	7,812.27	0.00	0.00	0.00
15,400.00	89.67	270.23	8,049.94	232.89	-7,908.99	7,912.25	0.00	0.00	0.00
15,500.00	89.67	270.23	8,050.52	233.30	-8,008.99	8,012.23	0.00	0.00	0.00
15,600.00	89.67	270.23	8,051.10	233.70	-8,108.98	8,112.21	0.00	0.00	0.00
15,700.00	89.67	270.23	8,051.69	234.11	-8,208.98	8,212.19	0.00	0.00	0.00
15,800.00	89.67	270.23	8,052.27	234.51	-8,308.98	8,312.17	0.00	0.00	0.00
15,900.00	89.67	270.23	8,052.85	234.92	-8,408.98	8,412.15	0.00	0.00	0.00
16,000.00	89.67	270.23	8,053.43	235.32	-8,508.97	8,512.13	0.00	0.00	0.00
16,100.00	89.67	270.23	8,054.02	235.73	-8,608.97	8,612.11	0.00	0.00	0.00
16,200.00	89.67	270.23	8,054.60	236.13	-8,708.97	8,712.09	0.00	0.00	0.00
16,300.00	89.67	270.23	8,055.18	236.54	-8,808.97	8,812.07	0.00	0.00	0.00
16,400.00	89.67	270.23	8,055.76	236.94	-8,908.96	8,912.05	0.00	0.00	0.00
16,500.00	89.67	270.23	8,056.35	237.35	-9,008.96	9,012.03	0.00	0.00	0.00
16,600.00	89.67	270.23	8,056.93	237.75	-9,108.96	9,112.01	0.00	0.00	0.00
16,700.00	89.67	270.23	8,057.51	238.16	-9,208.96	9,212.00	0.00	0.00	0.00
16,800.00	89.67	270.23	8,058.09	238.56	-9,308.95	9,311.98	0.00	0.00	0.00
16,900.00	89.67	270.23	8,058.68	238.97	-9,408.95	9,411.96	0.00	0.00	0.00
17,000.00	89.67	270.23	8,059.26	239.37	-9,508.95	9,511.94	0.00	0.00	0.00
17,100.00	89.67	270.23	8,059.84	239.78	-9,608.95	9,611.92	0.00	0.00	0.00
17,200.00	89.67	270.23	8,060.42	240.18	-9,708.94	9,711.90	0.00	0.00	0.00
17,300.00	89.67	270.23	8,061.01	240.59	-9,808.94	9,811.88	0.00	0.00	0.00
17,400.00	89.67	270.23	8,061.59	240.99	-9,908.94	9,911.86	0.00	0.00	0.00
17,500.00	89.67	270.23	8,062.17	241.40	-10,008.94	10,011.84	0.00	0.00	0.00
17,600.00	89.67	270.23	8,062.75	241.80	-10,108.93	10,111.82	0.00	0.00	0.00
17,700.00	89.67	270.23	8,063.34	242.21	-10,208.93	10,211.80	0.00	0.00	0.00
17,800.00	89.67	270.23	8,063.92	242.61	-10,308.93	10,311.78	0.00	0.00	0.00
17,900.00	89.67	270.23	8,064.50	243.02	-10,408.93	10,411.76	0.00	0.00	0.00
18,000.00	89.67	270.23	8,065.08	243.42	-10,508.92	10,511.74	0.00	0.00	0.00
18,100.00	89.67	270.23	8,065.66	243.83	-10,608.92	10,611.72	0.00	0.00	0.00
18,157.61	89.67	270.23	8,066.00	244.06	-10,666.53	10,669.32	0.00	0.00	0.00
BHL: 1532' FSL, 325' FWL									

ConocoPhillips

Planning Report

Database:	EDT 14 Central Planning	Local Co-ordinate Reference:	Well Rush 4-65 29-30 3DH
Company:	ConocoPhillips RBU Gold Data	TVD Reference:	25' RKB @ 5720.50ft (25' RKB)
Project:	Niobrara Central Zone	MD Reference:	25' RKB @ 5720.50ft (25' RKB)
Site:	Rush	North Reference:	True
Well:	Rush 4-65 29-30 3DH	Survey Calculation Method:	Minimum Curvature
Wellbore:	Rush 4-65 29-30 3DH		
Design:	Design A		

Design Targets

Target Name

- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- Shape									
Rush 4-65 29-30 3DH - plan hits target center - Point	0.00	0.00	8,009.00	204.41	-879.69	1,670,560.317	3,230,755.799	39° 40' 17.860 N	104° 40' 48.870 W
Rush 4-65 29-30 3DH - plan hits target center - Point	0.00	0.00	8,066.00	244.06	-10,666.53	1,670,511.316	3,220,969.170	39° 40' 18.230 N	104° 42' 54.030 W

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")
2,016.00	2,016.00	9-5/8" Casing	9-5/8	12-1/4
18,157.61	8,066.00	5-1/2" Casing	5-1/2	8-1/2

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,747.00	1,747.00	Fox Hills Top		0.00	
2,016.00	2,016.00	Pierre Top - Fox Hills Base		0.00	
2,216.00	2,216.00	Surface Casing		0.00	
7,878.71	7,809.00	Niobrara Top		0.00	
8,266.36	7,999.00	D Chalk Top		0.00	

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
100.00	100.00	0.00	0.00	SHL: 1331' FSL, 422' FWL
6,384.84	6,377.92	41.11	-83.96	EOB: 1372' FSL, 338' FWL
7,587.97	7,551.60	157.45	-321.57	KOP: 1488' FSL, 100' FWL
8,370.52	8,009.00	204.41	-879.69	BPI/LP: 1532' FSL, 460' FEL
18,157.61	8,066.00	244.06	-10,666.53	BHL: 1532' FSL, 325' FWL