RECEIVED
MAR 10 1966
OIL & GAS
CONSERVATION COMMISSION
00819395

PLUG AND ABANDONMENT PROGNOSIS
DIVIDE WATERFLOOD UNIT
UNIT NO. 1

PERTINENT DATA:

ELEV: 4105 KB
KB-CHF: 7'
T.D.: 4998'
CASING: Sfc - unknown
$5\frac{1}{2}$" (14#) at 4997'
TUBING: 2 3/8" (153 jts)

AFE: R-7065
PBTD: 4754'±

Last Test: On 1-31-66, tested 4 BO and 34 BWPD.

PROPOSED WORK:

1. Pull production equipment.

2. Locate 5 1/2" csg free point. Shoot off and recover.

3. Spot the following cement plugs:

   (a) 40 sx across Muddy at 4744'.
   (b) 30 sx across casing stub.
   (c) 30 sx across bottom of sfc. csg.
   (d) 10 sx at sfc.

4. Install abandonment marker.

5. Fill out attached form and mail to Division Exploitation Engineer.

D. B. O'Neill

C. L. Creager

R

RHR/djc
2-23-66
Denver, Colorado