



Plan of Development

Completions will utilize the RWF 311-15 pad for remote completions operations for the proposed wells on the RWF 12-9 Pad. The RWF 311-15 pad will be re-opened to accommodate temporary frac equipment including approximately thirty-two (32) five hundred barrel (500bbl) frac tanks. Excess material and topsoil will be stockpiled along the southwest corner of the pad location west of the proposed frac equipment. All existing production equipment will remain in place. Minor road maintenance may be required along the existing access prior to completions operations. Produced water for completions operations will be transported from the Clough Production Pit (Clough 44-16-694; COGCC Facility ID 467753) to the booster pump on the Clough 20 pad (COGCC Loc ID: 335068) where it would be pumped to the RWF 311-15 pad. TEP would utilize existing water infrastructure including one (1) ten-inch (10") temporary surface water supply pipeline (approx. 393') from the valve can south of the Clough 20 to the booster pump on location and one (1) ten-inch (10") temporary surface water supply pipeline (approx. 4,417') from the Clough 20 to the RWF 311-15 pad, to transport water to the RWF 311-15 pad. TEP would install five (5) 4.5-inch temporary surface steel frac lines (approx. 9,715' each) from the RWF 311-15 pad to the RWF 12-9 pad following existing access road where possible. The temporary surface frac lines will be sleeved through one (1) twelve-inch (12") steel casing pipe across the drainage east of the RMV 8-16 pad. All temporary surface steel frac lines will be removed within six (6) months following completions operations. The RWF 311-15 pad will be reclaimed within six (6) months following completion of planned operations on the pad or during the next growing season, unless future completions operations are approved at this location.

Legend

- Existing Water Pipeline
- Existing Road
- Proposed Frac Lines (5-4.5")
- Existing Well
- Propose Pad Edge
- Proposed Daylight Line
- Proposed Limit of Disturbance
- Existing Production Equipment
- Proposed Excess Stockpile
- Proposed Topsoil Stockpile
- Existing Fence
- Existing Limit of Disturbance
- Stormwater Controls
- Drainage
- Existing Pad
- Parcel Ownership

TEP Rocky Mountain LLC

**RWF 311-15 Frac Pad
Plan of Development Map
T6S R94W, Section 15**

April 14, 2020

