

P&A proposal:

Young 12-11350

- a) MIRU w/Service rig
- b) Pull tubing to 2,850 ft
- c) Pump and displace 15 sacks of cement @ 2,850 ft
- d) Pull tubing to 2,000 ft
- e) Tag cement
- f) Pull tubing
- g) Perf Squeeze holes @ 372 ft
- h) Pump cement down 4-1/2" csg through squeeze holes up annulus to surface
- i) Cut & cap