Proposed Wellbore Schematic

Well Name:	Rauth G	Date Prepared:	11/27/2021
Location:	2310' FNL, 2310' FEL, SWNE Sec 13, T9N, R58W	Last Updated:	11/27/2021
County	Weld	Spud Date:	5/11/1952
API #:	05-123-05661	Completion Start Date:	N/A
Co-ordinates:	40.752505 / -103.811024	Last Workover Date:	N/A
Elevations: GROUND:	4625'	Prepared by:	Jake Van Bramer
KB:	4635'	Updated by:	--
Depths (KB): PBTD:	--		
TD:	6218'		



PBTD - --'
TD - 6218'

Surface Casing:
Unknown Hole Size, assumed to be 15"
Landed 10-3/4", 32.75# casing at 270'
Cemented with 200 sks

Production Casing:
No production casing

Open Hole:
283'-6218', 8-5/8" hole size

Tubing:
None

Rods:
None

Perforations:
None

P&A Plugs:
1. 118 sks Class G (1.15 cuft/sk) from 5165'-5465' (new)
2. 60 sks Class G (1.15 cuft/sk) from 1500'-1650' (new)
3. 216 sks Class G (1.15 cuft/sk) from 400' to Surface (new)

Additional Notes:

Initial Potential Test:

Formation Tops:

Niobrara	5365'
D Sand	6134'