

Vision Energy, LLC
Bear Gulch 29-2
Garfield County
SE NE Section 29, T6S, R101W
COC-23072
API # 05-045-06450

1. Perform Bradenhead test on well.
2. Make road passable for rig and trucks.
3. Spot a minimum of 200' of cement from 720' up to 520' (100' below surface casing and 100' into surface casing (65 sacks of Class II neat).
4. Wait at least 1.5 hours and then tag cement top. If not at 520' or higher, top off with additional cement to get to that depth.
5. Excavate around surface casing and cut off casing 4' below grade.
6. Top off the 8 $\frac{5}{8}$ " casing with cement from 100' back to surface with 32 sacks of Class II neat cement.
7. Weld a steel marker plate with weep hole onto the casing stub. The marker plate is to be inscribed with the following information:

Maralex Resources, Inc./Vision Energy, LLC
Bear Gulch 29-2
COC 23072
SENE 29 6S 101W
05-045-06450

Regulatory Contacts:

BLM – Jim Annable O: 970.876.9033 C: 970.930.7188

COGCC – Aaron Katz O: 303.894.2100 ext. 5691 C: 970.765.6300