

State of Colorado
Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
403641229

Receive Date:
01/04/2024

Report taken by:
Steven Arauza

Site Investigation and Remediation Workplan (Initial Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: <u>CAERUS PICEANCE LLC</u>	Operator No: <u>10456</u>	Phone Numbers
Address: <u>1001 17TH STREET #1600</u>		Phone: <u>(970) 902-3598</u>
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>		Mobile: <u>()</u>
Contact Person: <u>Andy Verbonitz</u>	Email: <u>averbonitz@caerusoilandgas.com</u>	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 33899 Initial Form 27 Document #: 403641229

PURPOSE INFORMATION

- Rule 913.c.(1): Pit or Cuttings Trench closure.
- Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- Rule 913.g: Changes of Operator.
- Rule 915.b: Request to leave elevated inorganics in situ.
- Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: <u>SPILL OR RELEASE</u>	Facility ID: <u>485234</u>	API #: _____	County Name: <u>GARFIELD</u>
Facility Name: <u>MR29C water can N-59629C-200 4" tee</u>	Latitude: <u>39.584018</u>	Longitude: <u>-108.196386</u>	
	** correct Lat/Long if needed: Latitude: <u>39.584261</u>	Longitude: <u>-108.198164</u>	
QtrQtr: <u>nesw</u>	Sec: <u>29</u>	Twp: <u>5s</u>	Range: <u>96w</u> Meridian: <u>6</u> Sensitive Area? <u>Yes</u>

SITE CONDITIONS

General soil type - USCS Classifications SP Most Sensitive Adjacent Land Use non-cropland, rangeland

Is domestic water well within 1/4 mile? No Is surface water within 1/4 mile? No

Is groundwater less than 20 feet below ground surface? No

Other Potential Receptors within 1/4 mile

Elk winter range high priority habitat (HPH)

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- E&P Waste
- Other E&P Waste
- Non-E&P Waste
- Produced Water
- Workover Fluids
- Oil
- Tank Bottoms
- Condensate
- Pigging Waste
- Drilling Fluids
- Rig Wash
- Drill Cuttings
- Spent Filters
- Pit Bottoms
- Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	SOILS	undetermined	sampling and laboratory analysis

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Please refer to document numbers 403553343 and 403558784 for initial actions taken in support of this project. As described in the attached Site Investigation Report, One soil sample was collected under the point of release (POR) at a depth of approximately 10 feet below ground surface (bgs), as part of the initial investigation. Additionally, three background soil samples were collected for ECMC Table 915-1 Soil Suitability for Reclamation and Metals laboratory analysis from native areas around the site.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Additional soil samples are necessary to define the extent of impacts associated with the release. Due to the depth of impacts soil borings will be completed around the water can to a depth of up to 20 feet bgs. It is proposed that up to four soil borings be completed around and within the water can to define the extent of impacts

Proposed Groundwater Sampling

Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

[Empty text box for groundwater sampling details]

Proposed Surface Water Sampling

Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

[Empty text box for surface water sampling details]

Additional Investigative Actions

Additional alternative investigative actions described in attached Site Investigation Plan (summary):

[Empty text box for additional investigative actions]

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 6
Number of soil samples exceeding 915-1 1
Was the areal and vertical extent of soil contamination delineated? No
Approximate areal extent (square feet) 1

NA / ND

-- Highest concentration of TPH (mg/kg) 842
-- Highest concentration of SAR 18.9
BTEX > 915-1 Yes
Vertical Extent > 915-1 (in feet) 10

Groundwater

Number of groundwater samples collected 0
Was extent of groundwater contaminated delineated? No
Depth to groundwater (below ground surface, in feet) _____
Number of groundwater monitoring wells installed _____
Number of groundwater samples exceeding 915-1 _____

Highest concentration of Benzene (µg/l) _____
Highest concentration of Toluene (µg/l) _____
Highest concentration of Ethylbenzene (µg/l) _____
Highest concentration of Xylene (µg/l) _____
Highest concentration of Methane (mg/l) _____

Surface Water

0 Number of surface water samples collected
_____ Number of surface water samples exceeding 915-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

Were impacts to adjacent property or offsite impacts identified?

Were background samples collected as part of this site investigation?

Three background soil samples were collected for ECMC Table 915-1 Soil Suitability for Reclamation and Metals laboratory analysis from native areas around the site for comparison.

Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) _____ Volume of liquid waste (barrels) _____

Is further site investigation required?

Additional soil samples are necessary to define the extent of impacts associated with the release. Due to the depth of impacts soil borings will be completed around the water can to a depth of up to 20 feet bgs. It is proposed that up to four soil borings be completed around and within the water can to define the extent of impacts.

REMEDIAL ACTION PLAN

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Weld on 4" Tee was repaired.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Following additional soil assessment activities' a remedial approach will be proposed in a forthcoming form 27. Remedial approach may include in-situ or ex-situ approach based on assessment results.

Soil Remediation Summary

In Situ

Ex Situ

_____ Bioremediation (or enhanced bioremediation)

_____ Excavate and offsite disposal

_____ Chemical oxidation

If Yes: Estimated Volume (Cubic Yards) _____

_____ Air sparge / Soil vapor extraction

Name of Licensed Disposal Facility or COGCC Facility ID # _____

____ Natural Attenuation
____ Other _____

____ Excavate and onsite remediation
____ Land Treatment
____ Bioremediation (or enhanced bioremediation)
____ Chemical oxidation
____ Other _____

Groundwater Remediation Summary

____ Bioremediation (or enhanced bioremediation)
____ Chemical oxidation
____ Air sparge / Soil vapor extraction
____ Natural Attenuation
____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

Quarterly Semi-Annually Annually Other

Request Alternative Reporting Schedule:

Semi-Annually Annually Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type: Groundwater Monitoring Land Treatment Progress Report O&M Report
 Other _____

Adequacy of Operator's General Liability Insurance and Financial Assurance

Describe the adequacy of the Operator's general liability insurance and Financial Assurance to fully address the anticipated costs of Remediation, including the estimated remaining cost for this project (below).

If this information has been provided on a Form 27 within the last 12 months, provide the Document Number of that form.

Per Rule 705.b, and in line with guidance laid out in the SBAP, Caerus has general liability insurance in the amount of \$1M, and Caerus has umbrella insurance, which sits over the general liability insurance in the amount of \$75M. The umbrella and general liability insurance covers property damage, bodily injury to third parties, and sudden or accidental pollution under a combined \$76M.

Operator anticipates the remaining cost for this project to be: \$ 20000 _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards _____

E&P waste (solid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

Volume of E&P Waste (liquid) in barrels _____

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Once remediation is complete, any disturbed areas will be reclaimed in accordance with 1000 Series regulations.

Is the described reclamation complete? No _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

Interim Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. 03/31/2024

Proposed date of completion of Reclamation. 03/31/2024

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 10/06/2023

Actual Spill or Release date, or date of discovery. 10/06/2023

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 11/14/2023

Proposed site investigation commencement. _____

Proposed completion of site investigation. 11/14/2023

REMEDIAL ACTION DATES

Proposed start date of Remediation. 02/29/2024

Proposed date of completion of Remediation. 08/30/2024

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

OPERATOR COMMENT

Caerus believes a pathway to groundwater does not exist based on the following reasons and requests use of Table 915-1 Residential Soil Screening Level cleanup concentrations for future soil sample comparison:

- 1) Based on DWR data, depth to groundwater at the Site is estimated to be greater than 34 feet below ground surface (bgs). The closest permitted groundwater well receipt number 3654804B had a total depth of 34' bgs with no groundwater encountered.
 - 2) Source identified and repaired
 - 3) The closest surface water is Willow Creek which located approximately 1700' NW of the release and is approximately 400' lower in elevation.
- Based on lab results from the initial investigation, and in consideration of the request to utilize Table 915-1 Residential Soil Screening Level standards, Caerus requests a reduced soil sample analysis suite for the project to include TPH C6-C36 and SAR only.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Andy Verbonitz

Title: EHS Specialist

Submit Date: 01/04/2024

Email: averbonitz@caerusoilandgas.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Steven Arauza

Date: 01/30/2024

Remediation Project Number: 33899

COA Type

Description

	Submit Supplemental eForm 19 to request closure of Spill/Release ID #485234. Supplemental report shall comply with outstanding COAs, indicate that work is proceeding under an approved eForm 27 and shall reference the Remediation Project number assigned upon approval of this report.
	Operator shall collect soil samples from areas most likely to be impacted and shall collect an appropriate number of representative soil samples to delineate the horizontal and vertical extents of contamination, per Rule 915.e.(2).B.
	Per Rule 913.b.(2), the Operator will conduct sampling and analysis of soil, and groundwater--if encountered, to determine the horizontal and vertical extent of any contamination in excess of the cleanup concentrations in Table 915-1 for soil and groundwater. The Operator shall analyze samples for the approved analyte list and shall compare analytical results for site investigation samples to the Table 915-1 Residential Soil Screening Level Concentrations.
	Based on the analytical data provided for the point of release soil sample and estimated depth to groundwater (doc #403644449), the Operator's request for a reduced analyte suite of TPH (GRO/DRO/ORO) and SAR only is approved under the following condition: Operator will continue to analyze soil samples for EC in addition to the requested analytes.
4 COAs	

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

<u>Att Doc Num</u>	<u>Name</u>
403641229	INVESTIGATION/REMEDATION WORKPLAN (INITIAL)
403641499	SITE INVESTIGATION PLAN
403641500	SITE INVESTIGATION REPORT
403644449	OTHER
403671247	FORM 27-INITIAL-SUBMITTED

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)