

State of Colorado
Energy & Carbon Management Commission1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

403764690

Receive Date:

Report taken by:

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by ECMC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP	Operator No: 47120	Phone Numbers
Address: P O BOX 173779		Phone: (970) 336-3500
City: DENVER	State: CO	Zip: 80217-3779
Contact Person: Ariana Ochoa	Email: DJRemediation_Forms@oxy.com	Mobile: (713) 350-4906

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 31886 Initial Form 27 Document #: 403511584

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☐ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☐ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☒ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: WELL	Facility ID: _____	API #: 123-25100	County Name: WELD
Facility Name: CANEPA 6-21		Latitude: 40.260910	Longitude: -104.934670
		** correct Lat/Long if needed: Latitude: _____	Longitude: _____
QtrQtr: NENW	Sec: 6	Twp: 3N	Range: 67W
Meridian: 6	Sensitive Area? Yes		

SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Crop Land

Is domestic water well within 1/4 mile? No Is surface water within 1/4 mile? No

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Water Well: none
Surface Water: none
Wetlands: approximately 1035' SE
Springs: none
Livestock: none
Occupied Building: approximately 980' SW
High Priority Habitat (HPH): none

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- ☒ E&P Waste ☐ Other E&P Waste ☐ Non-E&P Waste
- ☒ Produced Water ☐ Workover Fluids
- ☒ Oil ☐ Tank Bottoms
- ☒ Condensate ☐ Pigging Waste
- ☐ Drilling Fluids ☐ Rig Wash
- ☐ Drill Cuttings ☐ Spent Filters
- ☐ Pit Bottoms
- ☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
No	GROUNDWATER	Groundwater not encountered	Groundwater samples/laboratory analytical results
No	SOILS	No impacted soils	Inspection/soil samples/laboratory analytical results

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Wellhead cut and cap operations were completed at the Canepa 6-21 wellhead on January 25, 2024. Groundwater was not encountered in the wellhead cut and cap excavation area. Visual inspection and field screening of soils around the well and associated pumping equipment was conducted following wellhead cut and cap operations, and a soil sample (WH-B01@6') was submitted for laboratory analysis to determine if a release occurred. The removal of the associated flowline was completed on January 24-29, 2024. Soil samples were collected from the locations where the flowline risers were disconnected at the wellhead (FL-B05@4') and separator (FL-B01@4'), and the directional change of the flowline (FL-B04@4') and submitted for laboratory analysis to determine if a release occurred. Laboratory analytical results indicated that constituent concentrations in the soil samples were in compliance with ECOM Table 915-1 standards and/or within background concentrations. A topographic Site Location Map showing the geographic setting of the site location is provided as Figure 1. Soil sample location and field screening data are presented in Table 1. The wellhead and soil sample and field screening locations are illustrated on Figure 2. The flowline soil sample and field screening locations are illustrated on Figure 3.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

- ☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

On January 25 - 29, 2024, soil samples were collected from the base of the cut and cap excavation area (WH-B01@6'), and from the locations where the flowline risers were disconnected at the wellhead (FL-B05@4') and separator (FL-B01@4'), and the directional change of the flowline (FL-B14@3'). The soil samples were submitted for laboratory analysis of the full ECOM Table 915-1 analytical suite. Analytical results indicated that constituent concentrations in the soil samples were in compliance with ECOM Table 915-1 standards and/or within local background concentrations. Soil analytical results are presented in Tables 2 - 5. The laboratory analytical reports are provided as Attachment A.

Proposed Groundwater Sampling

- ☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Groundwater was not encountered during decommissioning activities.

Proposed Surface Water Sampling

- ☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

- ☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

On January 24 - 29, 2024, visual inspection and field screening of soils was conducted at 4 sidewall locations within the cut and cap excavation area, 4 locations at the ground surface adjacent to the excavation, and 8 flowline removal potholes. Based on the inspection and screening results, hydrocarbon-impacted soil was not observed at the screening locations, and no soil samples were submitted for laboratory analysis from these areas in accordance with the ECOM Operator Guidance. On January 30, 2024, a soil gas survey was conducted at 5 soil vapor points (SVP01 - SVP05) installed adjacent to the former wellhead location following cut and cap operations. GEM 5000 field readings were non-detect for methane at all 5 soil vapor points. SVP locations are illustrated on Figure 2 and SVP screening results are presented in Table 6. The laboratory analytical report is provided as Attachment A. The field notes and photographic log are provided as Attachment B.

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 4

Number of soil samples exceeding 915-1 0

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 0

NA / ND

ND Highest concentration of TPH (mg/kg)

-- Highest concentration of SAR 2.46

BTEX > 915-1 No

Vertical Extent > 915-1 (in feet) 0

Groundwater

Number of groundwater samples collected 0

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet)

Number of groundwater monitoring wells installed

Number of groundwater samples exceeding 915-1

Highest concentration of Benzene (µg/l)

Highest concentration of Toluene (µg/l)

Highest concentration of Ethylbenzene (µg/l)

Highest concentration of Xylene (µg/l)

Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

 Number of surface water samples exceeding 915-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☒ Were background samples collected as part of this site investigation?

Background soil samples WH-BG01@3'-WH-BG04@3' and WH-BG01@6'-WH-BG04@6' were collected from native material adjacent to the wellhead cut and cap excavation. The background soil samples were submitted for laboratory analysis of the Soil Suitability for Reclamation Parameters and/or Table 915-1 Metals using standard methods appropriate for detecting the target analytes in Table 915-1. Analytical results for the background soil samples are presented in Tables 3 and 5.

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Laboratory results indicate that constituent concentrations in the soil samples collected from the base of the wellhead cut and cap excavation area (WH-B01@6') and during flowline removal (FL-B01@4', FL-B04@4', FL-B05@4') were in compliance with the ECMC Table 915-1 standards and/or within local background concentrations. The cut and cap excavation will be backfilled and contoured to match preexisting site conditions.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Laboratory results indicate that constituent concentrations in the soil samples collected from the base of the wellhead cut and cap excavation area (WH-B01@6') and during flowline removal (FL-B01@4', FL-B04@4', FL-B05@4') were in compliance with the ECMC Table 915-1 standards and/or within local background concentrations. Groundwater was not encountered in the cut and cap excavation area or flowline removal potholes. Based on the analytical and soil screening data presented herein, assessment is complete at this site and no further activities are required. As such, Kerr-McGee is requesting a No Further Action (NFA) determination for this location.

Soil Remediation Summary

<input type="checkbox"/> In Situ	<input type="checkbox"/> Ex Situ
_____ Bioremediation (or enhanced bioremediation)	_____ Excavate and offsite disposal
_____ Chemical oxidation	_____ If Yes: Estimated Volume (Cubic Yards) _____
_____ Air sparge / Soil vapor extraction	_____ Name of Licensed Disposal Facility or ECMC Facility ID # _____
_____ Natural Attenuation	_____ Excavate and onsite remediation
_____ Other _____	_____ Land Treatment
	_____ Bioremediation (or enhanced bioremediation)
	_____ Chemical oxidation
	_____ Other _____

Groundwater Remediation Summary

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Air sparge / Soil vapor extraction

_____ Natural Attenuation

_____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☐ Quarterly ☐ Semi-Annually ☐ Annually ☒ Other Final Report

☐ **Request Alternative Reporting Schedule:**

☐ Semi-Annually ☐ Annually ☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type: ☐ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report
☒ Other NFA Request

Adequacy of Operator's General Liability Insurance and Financial Assurance

Describe the adequacy of the Operator's general liability insurance and Financial Assurance to fully address the anticipated costs of Remediation, including the estimated remaining cost for this project (below).

If this information has been provided on a Form 27 within the last 12 months, provide the Document Number of that form.

KMOG has sufficient insurance and bonding to fully address the anticipated costs of Remediation, including the remaining estimated costs for this project. KMOG currently has over 40 million in bonds with the Energy & Carbon Management Commission. The cost for remediation is a preliminary estimate only, costs may change upwards or downward based on site specific information. KMOG makes no representation or guarantees as to the accuracy of the preliminary estimate.

Operator anticipates the remaining cost for this project to be: \$ 0

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards

E&P waste (solid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

Volume of E&P Waste (liquid) in barrels

E&P waste (liquid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? Yes

If YES:

☒ Compliant with Rule 913.h.(1).

☐ Compliant with Rule 913.h.(2).

☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? Yes

Does the previous reply indicate consideration of background concentrations? Yes

Does Groundwater meet Table 915-1 standards? Yes

Is additional groundwater monitoring to be conducted? _____

Operator shall comply with the ECMC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The site will be reclaimed in accordance with ECMC 1000 Series Reclamation Rules. Timeliness of reclamation initiation and completion will be subject to NFA, surface owner discretion and land use, and suitable ground conditions which allow for execution of surface reclamation activities so as to not cause unwarranted damages.

Is the described reclamation complete? No

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim

☐ Final

Did the Surface Owner provide the seed mix? Yes

If YES, does the seed mix comply with local soil conservation district recommendations? Yes

Did the local soil conservation district provide the seed mix? No

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. 07/25/2024

Proposed date of completion of Reclamation. 08/25/2024

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 08/22/2023

Actual Spill or Release date, or date of discovery. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 01/24/2024

Proposed site investigation commencement. 01/24/2024

Proposed completion of site investigation. 01/29/2024

REMEDIAL ACTION DATES

Proposed start date of Remediation. _____

Proposed date of completion of Remediation. _____

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☐ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

OPERATOR COMMENT

--

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Ariana Ochoa

Title: Sr. HSE Advisor

Submit Date:

Email: DJRemediation_Forms@oxy.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with ECOMC Rules and applicable orders and is hereby approved.

ECMC Approved:

Date:

Remediation Project Number: 31886

COA Type**Description**

0 COA	

ATTACHMENT LIST

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

403764691	PHOTO DOCUMENTATION
403764693	SITE MAP
403764695	SOIL SAMPLE LOCATION MAP
403764696	SOIL SAMPLE LOCATION MAP
403764699	ANALYTICAL RESULTS
403764701	ANALYTICAL RESULTS

Total Attach: 6 Files

General Comments**User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)